

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely

Make Required Affidavit


Mail or Deliver Report to

Conservation Division

State Corporation Comm.

245 North Water

Wichita, KS 67202

Locate well correctly on above
Section PlotHodgeman County, Sec. 25 Twp. 22S Rge. 25W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SW NE

Lease Owner Theodore I. Lehen Oil Operations

Lease Name Sheppard Well No. 1

Office Address 1555 E. Second, Wichita, Ks. 67214

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed 6-27 1976

Application for plugging filed 6-27 1976

Application for plugging approved 6-27 1976

Plugging commenced 6-27 1976

Plugging completed 6-27 1976

Reason for abandonment of well or producing formation

No commercial quantities of oil or gas encountered.

If a producing well is abandoned, date of last production
19Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas

Producing formation Depth to top Bottom Total Depth of Well 4680

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Shale	Sur.	428	8-5/8	420	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

plug
Fluid to 900', /50 sx cement;

Fluid to 400', plug, 35 sx cement;

Fluid to 40', plug, 15 sx cement;

Five sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

JUL 08 1976 7-8-76

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

D N B DRILLING, INC.

701 First National Building

Wichita, Kansas 67202

STATE OF KANSAS

COUNTY OF

ss.

JAMES L. DONELSON

(employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

701 First National Bldg., Wichita, Ks. 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of June, 1976

Ella Priess

Notary Public.

My commission expires 8-25-76

Ella Priess

Ella Priess
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Com. Expires Aug. 25, 1976

DRILLERS' LOG

THEODORE I. LEBEN OIL OPERATIONS
 No. 1 Sheppard
 C-SW NE, Sec. 25-22S-25W
 Hodgeman County, Kansas

Elev: 2485 G.L.

Commenced: 6-20-76
 Completed: 6-27-76

Surface Casing: 420' of 8-5/8"
 cemented w/250 sx common cement,
 2% Gel, 3% cc. 6-20-76

FORMATIONDEPTH

Surface Hole	0 - 428
Shale & Red Beds	428 - 1012
Shale	1012 - 1054
Blaine Anhydrite	1054 - 1068
Shale & Red Bed & Sand	1068 - 1655
Anhydrite	1655 - 1687
Shale	1687 - 2250
Lime & Shale	2250 - 3940
Lime	3940 - 4680 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D. N. B. DRILLING, INC.


James L. Donelson
 JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 30th day of June, 1976.

Ella Priess

Ella Priess, Notary Public



RECEIVED
 OFFICE OF THE SECRETARY OF STATE
 KANSAS

CONSERVATION DIVISION
 Wichita, Kansas