

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-083-21,207-0000

LEASE NAME Bohling

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 24 TWP. 22 RGE. 25 (N or W)

COUNTY Hodgeman

Date Well Completed 9-1-85

Plugging Commenced 9-1-85

Plugging Completed 9-1-85

LEASE OPERATOR Vincent Oil Corporation

ADDRESS 125 N. Market - Suite 1110, Wichita, Kansas 67202

PHONE#(316) 262-3573 OPERATORS LICENSE NO. 5004

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas-Steve Durrant

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	601	8 5/8	8-21-85	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well with 200 sxs 60/40 poz, 6% gel as follows: 1700'-50 sxs; 1400'-75 sxs; 730'-50 sxs; 40'-10 sxs with solid bridge; rathole-15 sxs. Job by Allied Cementing Co. Complete at 2:00 p.m. on September 1, 1985.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149


Address P. O. Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Arnie Little (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Arnie Little

(Address) P. O. Box 329, Pratt, Kansas 67124



SUBSCRIBED AND SWORN TO before me this 25th day of September, 1985

Mary L. Tjaden

My Commission Expires: 3/22/88

STATE CORPORATION COMMISSION

SEP 26 1985

9-26-85

Form CP-4

Revised 08-84

CONSERVATION DIVISION



Oilfield Services, Inc.

15-083-21207-0000

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Bohling #1
C NE NW Sec. 24-22S-25W
Hodgeman County, Kansas
Commenced: 8-20-85
Completed: 9-1-85
API #15-083-21,207
Operator: Vincent Oil Corporation

Depth		Formation	Remarks
From	To		
0	610	Sand, Clay, Shale	Ran 14 joints (591') new, 23#,
610	1675	Clay	8 5/8" casing set at 601' with 250
1675	2270	Shale, Lime	sx Lite, 100 sx Class A, 2% gel,
2270	2525	Shale	3% cc. Plug down at 2:45 a.m.,
2525	4677	Shale, Lime	8-21-85. Did circulate. Job by
		T.D.	Allied Cementing, Great Bend.


RTD 4677'.


Plugged well with 200 sx, 60/40 poz, 6% gel as follows: 1700'-50 sx; 1400'-75 sx; 730'-50 sx; 40'-10 sx; rathole-15 sx. Job by Allied Cementing. Complete at 2:00 p.m. on 9-1-85. State plugger was out of the Dodge City, Kansas office.

STATE OF KANSAS)
COUNTY OF PRATT) ss

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.


ARNIE LITTLE, VICE-PRESIDENT


NOTARY PUBLIC

My Commission Expires:

3/22/88



RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1985

CONSERVATION DIVISION
316 672-7514