

6-16-88 15-055-10123-0006 179 R

1 051063

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 12-16-55

NE SE SW, SEC. 21, T 22 S, R 33 W/EX

990 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565 Lease Name Damme Well # 4

Operator: National Cooperative Refinery Assoc. County Finney 158.11

Name & Address Box 6 Well Total Depth 4865 feet

Great Bend, KS 67530 Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 341

Abandoned Oil Well Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 16 Month: 6 Year: 19 88

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4684' PBTD 4831' Perfs at 4691-4721' Elevation 2898' RB DV tool at 2746' with 275 sx cement.

1st plug sand back to 4640' with 5 sx cement,

2nd plug pump 400 lbs. hulls and 100 sx econolite cement in 5 1/2",

3rd plug pump 100 sx cement in 8 5/8" X 5 1/2" annulus.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2 p.m. Day: 16 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4640' and dumped 5 sx cement on top of sand through bailer,

2nd plug shot pipe at 1700' and 950', pumped down 5 1/2" with 30 sx cement followed by

70 sx cement with 400 lbs. hulls mixed in. Maximum pressure 700 psi and shut in 200 psi.

3rd plug pumped 100 sx cement down 8 5/8" X 5 1/2" annulus. Maximum pressure 500 psi and shut in 100 psi.

STATE CORPORATION COMMISSION

Remarks: Used Econolite cement by Allied. No casing recovery. JUN 22 1988 (If additional description is necessary, use BACK of this form.)

INVOICED (XXXXXX) observe this plugging.

Signed Richard Lowry (TECHNICIAN) 6-22-88 CONSERVATION DIVISION Wichita, Kansas

DATE 7-13-88

INV. NO. 21329