

1080321

15-055-00116-0001

TO: STATE CORPORATION COMMISSION

API NUMBER DRILLED 12-11-54
C SE SE'NW SEC. 21, T 22 S, R 33 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME DAMME WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY FINNEY 156.33

OPERATOR LICENSE # 30535 7/7

WELL TOTAL DEPTH 4810 FEET

OPERATOR: HARTMAN OIL CO.

PRODUCTION CSG: SIZE 5 1/2" @ 4782' WITH 225 SX

NAME AND PO BOX 54

SURFACE CASING: SIZE 13 3/8" @ 240' WITH 200 SX

ADDRESS WICHITA, KS 67201

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR GONZALES WELL SERVICE LICENSE NUMBER 31985

ADDRESS PO BOX 2441 LIBERAL, KS 67905

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 07 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM STAN MITCHELL

(COMPANY NAME) GONZALES WELL SERVICE (PHONE) 316-353-8022

WERE: CASING LEAK AT 1508' SQUEEZED W/85 SX. STAGE COLLOR AT 2900' W/225 SX. CIBP @ 2616 PERFS AT 2490-96, 2524-32, 2540-50

RUN TUBING IN HOLE TO 2555'. PUMP 25 SX 60/40 6% GEL & 2%CC WITH 100# HULLS MIXED IN.

PERFORATE AT 1150' & 650'. PULLED TUBING TO 1165'. PUMP 120 SX CEMENT. CIRCULATE CEMENT TO

SURFACE ON INSIDE OF 5 1/2. PULLED TUBING OUT OF HOLE. PUT SWEDGE OF 5 1/2 PUMPED 100 SX CEMENT.

MAXIMUM PSI 500#. SHUT IN @ 350#. PUMPED DOWN 13 3/8 X 5 1/2 ANNULUS 205 SX CEMENT. MAXIMUM PSI

100#. SHUT IN @ 50#.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:45 PM DAY: 07 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT

RAN TUBING IN HOLE TO 2555'. PUMP 25 SX 60/40 6% GEL & 2% CC WITH 100# HULLS MIXED IN.

PERFORATE AT 1150' & 650'. PULLED TUBING TO 1165'. PUMPED 120 SX CEMENT CIRCULATED CEMENT

TO SURFACE ON INSIDE OF 5 1/2. PULLED TUBING OUT OF HOLE. PUT SWEDGE OF 5 1/2 PUMPED 100 SX CMT

MAXIMUM PSI 500#. SHUT IN # 350#. PUMPED DOWN 13 3/8 X 5 1/2 ANNULUS 205 SX CEMENT. MAXIMUM

PSI 100#. SHUT IN AT 50#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALIATED NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

DATE 7/25/00 SIGNED Kevin P. Strube

(TECHNICIAN)

FORM CPG2/SERVAT/CON DIVISION

WVZ NO. 1060123

RECEIVED STATE CORPORATION COMMISSION JUL 24 2000