

1080252

15-055-10046-0001

TO:  
STATE CORPORATION COMMISSIONAPI NUMBER DRILLED IN 10-4-56  
SE NE SE SEC. 21, T 22 S, R 33 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME DAMME WELL # 5

TECHNICIAN'S PLUGGING REPORT

COUNTY FINNEY 154.38

OPERATOR LICENSE # 30535

WELL TOTAL DEPTH 4750 FEET

OPERATOR: HARTMAN OIL CO., INC

PRODUCTION CSG: SIZE 5 1/2" @ 4750' WITH 600 SX

NAME AND PO BOX 54

SURFACE CASING: SIZE 8 5/8" @ 281' WITH 200 SX

ADDRESS WICHITA, KS 67201

ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐ SWD WELL ☐ D/A ☐

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR POST &amp; MASTIN WELL SERVICE INC LICENSE NUMBER 8438

ADDRESS 3210 W JONES AVE GARDEN CITY, KS 67846

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 17 MONTH: 06 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM STAN MITCHELL

(COMPANY NAME) POST &amp; MASTIN WELL SERVICE INC (PHONE) 316-276-3801

WERE: PERFS AT 4657-61, 4650-54, 4605-11, 4409-13, 4375-78 DV TOOL @ 2649

1ST PLUG PERFORATE AT 1100' 2 HOLE. RUN TUBING TO 4506'. PUMP BOTTOM PLUG 25 SX 60/40 6%

3% CC 100# HULLS. 2ND PLUG PULL TUBING TO 1110' PUMP 150 SX CEMENT CIRCULATE TO SURFACE.

PULL UP TO 300' PUMP 25 SX CEMENT. PULL TUBING OUT OF HOLE. PUMP DOWN 5 1/2" CASING 25 SX

CEMENT. PSI 450#. SHUT IN @ 250#. DIG OUT BRAIDEN HEAD. PUMP DOWN 8 5/8" X 5 1/2" ANNULUS 100

SX CEMENT. MAX PSI @ 500#. SHUT IN 250#. PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL ☒ PART ☐ NONE ☐

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 17 MONTH: 06 YEAR: 1999

ACTUAL PLUGGING REPORT 1ST PLUG LOG TECH OF KANSAS PERFORATED AT 1100' 2 HOLE. RAN TUBING

TO 4506' PUMPED BOTTOM PLUG 25 SX CEMENT 60/40 6% 3% CC 100# HULLS. 2ND PLUG PULLED TUBING

TO 1110' PUMPED 150 SX CEMENT CIRCULATED TO SURFACE PULLED UP TO 300' PUMPED 25 SX CEMENT

PULLED TUBING OUT OF HOLE. PUMPED DOWN 5 1/2" CASING 25 SX CEMENT. MAXIMUM PSI @ 450#. SHUT

IN WITH 250#. DUG OUT BRAIDEN HEAD. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 100 SX CEMENT. MAXIMUM

PSI 500#. SHUT IN @ 250#.

REMARKS: USED 60/40 POZMIX 6% GEL 3% CC ALLIED. NO CASING RECOVERED.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DMD) OBSERVE THIS PLUGGING.

SIGNED

(TECHNICIAN)

FORM CP-2/3

DATE 6-28-99

INV. NO. 61098

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 25 1999  
CONSERVATION DIVISION  
WICHITA, KS