

To: 1 051540 4-1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-055-00288-0000 Drilled 1951 78p
API NUMBER 15-
SW SW NE, SEC. 21, T. 22 S, R 33 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 30535
Operator: Hartman Oil Company, Inc.
Name & Address P.O. Box 869
Great Bend, KS 67530

2970 feet from S section line
2310 feet from E section line
Lease Name Damme Well # 2
County Finney
Well Total Depth 2710 88.0' feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 13 3/8 feet 295

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____
Address N. Highway 283, Ness City, KS

Company to plug at: Hour: 10:30 a.m. Day: 1 Month: 4 Year: 19 92

Plugging proposal received from Bill Blessing
(company name) Hartman Oil Company, Inc. (phone) 316-792-1108

were: 8 5/8" at 2710' w/350 sx cement, PBDT 2614.5', Perfs at 2540-52, 2523-35'
Pump-through tubing:

1st plug at 2500' with 40 sx cement and 30 sx gel,
2nd plug at 1500' with 40 sx cement,
3rd plug pump down 8 5/8" with 300 sx cement, 4th plug pump down 8 5/8" X 13 3/8" annulus with
125 sx cement. Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 3:30 p.m. Day: 1 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 8 5/8" casing leak at 1642-46' and 945'.
Sanded back to 2776', ran tubing to 2472' and pumped 30 sx gel followed by 40 sx cement.
Pulled tubing to 1510' and pumped 40 sx cement. Waited 3 hours for cement to set. Swedged
into 8 5/8" and pumped 300 sx cement. Maximum pressure 500 psi and shut in 200 psi.
Pumped 125 sx cement down 8 5/8" X 13 3/8" annulus. Maximum pressure 100 psi and shut in
50 psi.

Remarks: Used 60/40 Pozmix 6% gel 3% cc by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
I did observe this plugging.

DATE 5-4-92
INV. NO. 35123

Signed Richard W. Lacey
(TECHNICIAN) 4-6-92

