

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21230-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 17-22S-33W
2310 feet from N Section Line, 330 feet from W Section Line
Lease/Unit Name: GARDEN CITY C Well Number: 1-17
County: FINNEY Total Vertical Depth: 4830 feet

Operator License No.: 5210
Op Name: LEBSACK OIL PRODUCTION, INC.
Address: BOX 489 1303 MAIN ST.
HAYS, KS 67601

Conductor Pipe: Size 13.375 feet: 142 \$156.98
Surface Casing: Size 8.625 feet: 268 60/40 POZ CMT. TOP 3360
Production: Size 5.5 feet: 4829 TOP 3340 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/13/2002 10:15 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: WAYNE LEBSACK Company: LEBSACK OIL PRODUCTION Phone: (620) 938-2396

Proposed Plugging Method: PUMP 500# HULLS & 25 SX CMT ON BOTTOM. GEL SPACER TO 2700'. CMT FROM 2700' TO 0' INSIDE 5 1/2". PUMP DOWN 8 5/8" X 5 1/2" ANNULUS 50 SX CMT IF NEEDED. PRESSURE TEST 8 5/8" X 13 3/8" ANNULUS WITH CMT.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/13/2002 11:30 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PBTD 4789'. PERFS AT 4749-55'. DV TOOL @ 2710' WITH 405 SX CMT. CMT CIRCULATED TO SURFACE. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 10 SX CMT. PRESSURED UP TO 500#. PUMPED DOWN 5 1/2" CASING 300# HULLS & 25 SX CMT. PUMP 13 SX GEL TO 2700'. CMT WITH 265 SX CMT TO SURFACE. MAXIMUM PRESSURE 350#. SHUT IN. WELL ON SMALL VACUUM. LET CMT SET. CMT DOWN TO 250'. TOPPED OFF WITH READY MIX 1 1/2 YARDS. 13 3/8" X 8 5/8" ANNULUS CMT AT SURFACE.

RECEIVED
DEC 18 2002
KCC WICHITA
10-18-02

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed Kevin D Strube
(TECHNICIAN)

INVOICED
DATE 12-19-02
INV. NO. 2003060956

Form CR-2