

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-055-21,379-0000  
SE NW NW, SEC. 17, T 22 S, R 33 W/EK

12-15

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210  
Operator: Lebsack Oil Production Inc.  
Name:  
Address P.O. Box 489  
Hays, KS 67601

4290 feet from S section line  
4290 feet from E section line  
Lease Name Garden City C Well # 2-17  
County Finney  
Well Total Depth 4820 156.65 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 2:30 p.m. Day: 15 Month: 12 Year: 19 95

Plugging proposal received from Wayne Lebsack

(company name) Lebsack Oil Production Inc. (phone) 913-625-5444

logs: 5 1/2" at 4820' w/210 sx cement, Cementing collar at 2104' w/455 sx cement,

RECEIVED  
KANSAS CORPORATION COMMISSION

Perfs at 4722-30, 4678-82, 4412-20'

DEC 21 1995 12-21-95

1st plug pump in 5 1/2" casing with 300 lbs. hulls, 25 sx cement, 20 sx gel, and 200 sx cement,

CONSERVATION DIVISION  
WICHITA, KS

2nd plug pump 50 sx cement down 8 5/8" X 5 1/2" annulus.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 15 Month: 12 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls and 25 sx cement, to bottom,

2nd plug pumped 20 sx gel spacer and 200 sx cement. Shut in pressure 1900 psi.

3rd plug pumped 10 sx cement down 8 5/8" X 5 1/2" annulus. 500# pressure on backside.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby acknowledge and agree to observe this plugging.

DATE 1-8-96

Signed Kevin D. Smith (TECHNICIAN)

INV. NO. 44444