

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-10059-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 17-22S-33W  
330 feet from N Section Line, 330 feet from W Section Line  
Lease/Unit Name: FINNUP B Well Number: 6  
County: FINNEY Total Vertical Depth: 4875 feet

Operator License No.: 30535  
Operator Name: HARTMAN OIL CO., INC.  
Address: BOX 54  
WICHITA, KS 67201

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 386  
Production: Size 4.5 feet: 4875  
Liner: Size \_\_\_\_\_ feet: 158,44

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/29/2000 10:00:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: STAN MITCHELL Company: HARTMAN OIL Phone: (316) 636-2090

Proposed Plugging Method: PLUG BACK WITH SAND TO 3900'. PERFORATE AT 1101-03'. MIX 150 SX CMT PUMP DOWN 4 1/2" CASING. CIRCULATE TO SURFACE. MIX 200 SX CMT. PUMP DOWN ANNULUS. SHUT IN.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/29/2000 11:30 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 4761-65. 2" TUBING FROM 4532 - TD. DV TOOL AT 2716'. HAD FILL UP TO 4080'. PUT 15 SX SAND DOWN & FILLED UP TO 3800'. PERFORATED BY HALLIBURTON AT 1100' ON 09/22/00. ALLIED PUMPED DOWN 4 1/2 60 SX CMT AND THEN STARTED MIXING HULLS IN WITH 90 SX CMT. USED 300# HULLS. 4 1/2 ON VACUUM, SHUT IN. PUMPED DOWN 8 5/8 X 4 1/2 ANNULUS 200 SX CMT. MAXIMUM PRESSURE 200#. SHUT IN WITH 50#. TOPPED OFF WITH 3 1/2 YARDS OF READY MIX ON 10/2/00. CEMENT TOP WAS 800' DOWN.

10-6-00

RECEIVED  
STATE CORPORATION COMMISSION

OCT 6 2000

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Kevin D. Strube

(TECHNICIAN)

INVOICED

DATE

10/9/00

INV. NO.

2001060802

OCT 03 2000

MP

[Signature]