

To: - 1 090517 1-18  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
1200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 055-21,378 - 0000  
NE NE SE, SEC. 18, T 22 S, R 33 W EX  
2310 feet from S section line  
330 feet from E section line  
Lease Name Garden City D Well # 1-18  
County Finney 157.63  
Well Total Depth 4850 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 260

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5210  
Operator: Lebsack Oil Production Inc.  
Name & Address P.O.Box 489  
Hays, KS 67601

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_ X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie RTD, Inc. License Number 30684  
Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: 8 p.m. Day: 18 Month: 1 Year: 19 95

Plugging proposal received from Gary Fisher  
(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe  
1st plug at 3500' with 100 sx cement, 2nd plug at 2005' with 50 sx cement,  
3rd plug at 1100' with 80 sx cement, 4th plug at 600' with 40 sx cement,  
5th plug at 290' with 50 sx cement, 6th plug at 40-0' with 10 sx cement,  
7th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:30 p.m. Day: 18 Month: 1 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug at 3500' with 100 sx cement,  
2nd plug at 2005' with 50 sx cement, 3rd plug at 1100' with 80 sx cement,  
4th plug at 600' with 40 sx cement, 5th plug at 290' with 50 sx cement,  
6th plug at 40-0' with 10 sx cement,  
7th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.  
(if additional description is necessary, use BACK of this form)

INVOICED  
(if not observed) observe this plugging.

DATE 2-3-95  
INV. NO. 42145  
1-18

Signed [Signature] (TECHNICIAN)  
JAN 24 1995  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION FORM COB-213  
WICHITA, KANSAS Rev. 01-84

EFFECTIVE DATE: 1-11-95

DISTRICT # 1

SGA? Yes  No

State of Kansas 15-055-21,378-0000

FORM MUST BE SIGNED ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date 01 month 20 day 95 year

Spot NE East NE West SE Sec 18 Twp 22 S, Rg 33 XX

OPERATOR: License # 5210  
Name: Lebsack Oil Production Inc.  
Address: P.O. Box 489  
City/State/Zip: Hays, Ks. 67601  
Contact Person: Rex Curtis  
Phone: 913-625-5444

2310 feet from South / ~~North~~ line of Section  
330 feet from East / ~~West~~ line of Section  
IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License #: 30684  
Name: Abercrombie RTD, Inc.

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Finney  
Lease Name: Garden City "D" Well #: 1-18

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Enh Rec ... Infield  Mud Rotary  
... Gas ... Storage  Pool Ext. ... Air Rotary  
... GWO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes ... Other  
If GWO: old well information as follows:  
Operator: N/A  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Field Name: \_\_\_\_\_  
Is this a Prorated/Spaced Field? ... yes  no   
Target Formation(s): Mississippi  
Nearest lease or unit boundary: 320'  
Ground Surface Elevation: Unknown feet MSL  
Water well within one-quarter mile: ... yes  no   
Public water supply well within one mile: ... yes  no   
Depth to bottom of fresh water: 200'  
Depth to bottom of usable water: 1100'  
Surface Pipe by Alternate: ... 1  2  
Length of Surface Pipe Planned to be set: 250  
Length of Conductor pipe required: 4900'  
Projected Total Depth: \_\_\_\_\_  
Formation at Total Depth: Mississippi  
Water Source for Drilling Operations:  
... well ... farm pond  other

Directional, Deviated or Horizontal wellbore? ... yes  no   
If yes, true vertical depth: \_\_\_\_\_  
Bottom Hole Location: N/A  
Exp. 7/6/95

Will Cores Be Taken?: ... yes  no   
If yes, proposed zone: \_\_\_\_\_  
220' Alt. II Req.

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

- 1. Notify the appropriate district office prior to completion of well.

Pusher Larry SPUD DATE 1-11-1995 INIT. GB  
LENGTH SURFACE PLANNED 250 f  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE \_\_\_\_\_  
SURFACE PIPE 8 3/4 @ 260 CONDUCTOR \_\_\_\_\_  
ANHYDRITE T- B ELEVATION \_\_\_\_\_  
TD 4850 FORMATION MISS  
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N  
Arbuckle Plug @ \_\_\_\_\_ Ft. W/ SX  
1 Hug./Council @ 3500 Ft. W/ 100 SX  
2 Anhydrite Base @ 2005 Ft. W/ 30 SX  
3 1/2 Base Anhy. @ 1100 Ft. W/ 80 SX  
4 1/2, 1/2 Plug @ 600 Ft. W/ 40 SX  
5 Bottom Surface @ 290 Ft. W/ 50 SX  
6 40' Plug @ 40-0 Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 15 SX  
WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
Hauling \_\_\_\_\_  
TECHNICIAN JM DATE 1-17-95  
TYPE OF CEMENT 60/40 67 1/4 Global  
STARTING TIME 8:00 (AM/PM) DATE 1-18-95  
COMPLETION TIME 11:30 (AM/PM) DATE 1-18-95  
CEMENT COMPANY ACCIED

STATE RECEIVED 55-101, RECEIVED CORPORATION

STATE RECEIVED RECEIVED COMMISSION