

To: 1 090358 11-16
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 055-21,150-0000
E/2 NE NW, SEC. 18, T. 22 S, R. 33 W
4620 feet from S section line
2960 feet from E section line
Lease Name Garden City B Well # 1-18
County Finney
Well Total Depth 4820 156.65 feet
Conductor Pipe: Size 13 3/8 feet 102
Surface Casing: Size 8 5/8 feet 302.5

TECHNICIAN'S PLUGGING REPORT
Operator License # 5210
Operator: Lebsack Oil Production Inc.
Name:
Address P.O. Box 489
Hays, KS 67601

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Co. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:10 a.m. Day: 16 Month: 11 Year: 1993

Plugging proposal received from Manny Boatright
(company name) Kelso Casing Pulling Co. (phone) 316-938-2943

Work: 4 1/2" at 4806' with 160 sx cement, Perfs at 4425-30, 4360-66'
1st plug sand back to 4310' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 50 sx cement at 2010', 3rd plug pump 80 sx cement at 1100',
4th plug pump 50 sx cement at 330', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 2:45 p.m. Day: 16 Month: 11 Year: 1993.

ACTUAL PLUGGING REPORT 1st plug sanded back to 4310' and dumped 4 sx cement on top of sand
through bailer, spot plugs through casing:
2nd plug at 2005' with 50 sx cement,
3rd plug at 1110' with 80 sx cement,
4th plug at 330' with 50 sx cement,
5th plug at 40' with 10 sx cement. Circulated cement.

11-18-93

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

NOV 18 1993

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

I (did / observe this plugging.

DATE 11-18-93
INV. NO. 39260

Signed [Signature] (TECHNICIAN)