

To: **1 090537**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER **19-** Spud date 12/11/62

NE NE NE, SEC. 18, T 22 S, R 33 W/EX

4950 feet from S section line

330 feet from E section line

Lease Name Garden City A Well # 2

County Finney

Well Total Depth 4870 158.28 feet

Conductor Pipe: Size 13 3/8 feet?, cement circ.

Surface Casing: Size 8 5/8 feet 383

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210

Operator: Lebsack Oil Production, Inc.

Name & Address P.O. Box 489

Hays, KS 67601

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Post & Mastin Well Service License Number 8438

Address P.O. Box 297, Garden City, KS 67846

Company to plug at: Hour: 1:15 p.m. Day: 12 Month: 4 Year: 19 95

Plugging proposal received from Bert Mastin

(company name) Post & Mastin Well Service (phone) 316-276-3442

logs: 5 1/2" at 4868' w/300 sx cement, Perfs at 4772-77, 4418-22, DV tool at 2697' w/400 sx cmt.

1st plug pump down 5 1/2" casing with 4 sx hulls, gel to 2000', cement to surface.

Check backside.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:05 p.m. Day: 12 Month: 4 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 3 sx hulls, 40 sx cement, gel to 2100', and 175 sx cement to surface.

Maximum pressure 400 psi and shut in 0 psi.

Pressured backside to 500#.

RECEIVED
KANSAS CORPORATION COMMISSION

APR 14 1995

CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 4-26-95
INV. NO. 42694
observe this plugging.

Signed [Signature]
(TECHNICIAN)