

1050904

15-055-00091-0600 5-19-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion 11/17/53

SW SW SW, SEC. 25, T 22 S, R 23 ³³ ~~23~~ (W/D)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5693

330 feet from S section line

4950 feet from E section line

Operator: W.L. Hartman Trust

Lease Name Holsted Thomas Hill # 1

Name & Address P.O. Box 54

County Finney 159.41

Wichita, KS 67201

Well Total Depth 4905 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 265

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number NA

Address Box 420, Ness City, KS 67560

Company to plug at: Hour: 9 a.m. Day: 19 Month: 5 Year: 19 87

Plugging proposal received from Bob Rowley

(company name) W.L. Hartman Trust (phone) 316-277-2511

were: 5 1/2" at 4670' PBD 4432' Perfs at 4612-18, 4398-4402' Elevation 2870'

1st plug pump 3 sx hulls and 20 sx ATL to 4300', perforate at 1207',

2nd plug pump 100 sx ATL down 5 1/2",

3rd plug pump 2 sx hulls and 80 sx ATL down 10 3/4" X 5 1/2".

RECEIVED STATE CORPORATION COMMISSION MAY 22 1987 CONSERVATION DIVISION Wichita, Kansas

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3 p.m. Day: 19 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 3 sx hulls and 20 sx ATL cement and displaced to 4300', perforated at 1207', 2nd plug pumped 100 sx ATL down 5 1/2"-maximum pressure 500 psi and shut in 100 psi,

3rd plug pumped 2 sx hulls and 80 sx ATL down 10 3/4" X 5 1/2"-maximum pressure 400 psi and shut in 300 psi.

Remarks: Used ATL cement by Allied. No recovery. (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE 5-27-87

INV. NO. 16992