

To: 121046 6-28  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 13-055-21,420-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003  
Operator: McCoy Petroleum Corporation  
Name & Address: 3017 N. Cypress  
Wichita, KS 67226-4003

SE SE NE, SEC. 28, T. 22 S, R. 34 W/E  
2970 feet from S section line  
330 feet from E section line  
Lease Name Anderson PX Well # 1-28  
County Finney  
Well Total Depth 4880 158.60 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1685

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sweetman Drilling, Inc. License Number 5658

Address 3017 N. Cypress, Wichita, KS 67226

Company to plug at: Hour: \_\_\_\_\_ Day: 27 Month: 6 Year: 1995

Plugging proposal received from Eugene Saloga

(company name) Sweetman Drilling, Inc. (phone) 316-636-2737

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2000-2020'

- 1st plug at Hugoton/Council Grove base with 100 sx cement,
- 2nd plug at 2020' with 50 sx cement, 3rd plug at 1700' with 50 sx cement,
- 4th plug at 1000' with 40 sx cement, 5th plug at 40' with 10 sx cement,
- 6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:30 a.m. Day: 28 Month: 6 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 3200' with 100 sx cement,

2nd plug at 2020' with 50 sx cement, 3rd plug at 1700' with 50 sx cement,

4th plug at 1000' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

**INVOICED**

(Do not observe this plugging.)

DATE 7-7-95

Signed Duane Rankin  
(TECHNICIAN)

INV. NO. 43044

RECEIVED  
STATE CORPORATION COMMISSION

JUN 30 1995

6-30-95

STATE CORPORATION COMMISSION  
WICHITA, KANSAS

EFFECTIVE DATE: 6-18-95

15-055-21,420-0000  
State of Kansas

FORM MUST BE TYPE

NOTICE OF INTENTION TO DRILL DIST #1

ALL BLANKS MUST BE FILLED SGA7... Yes... No Must be approved by the K.C.

five (5) days prior to commencing well

Expected Spud Date 6 15 95  
month day year

Spot SE SE NE Sec 28 Twp 22S S. Rg 34 E2S  
SE

OPERATOR: License # 5003  
Name: McCoy Petroleum Corporation  
Address: 3017 N. Cypress  
City/State/Zip: Wichita, KS 67226-4003  
Contact Person: Roger McCoy  
Phone: (316) 636-2737

2970 feet from South line of Section  
330 feet from East line of Section  
IS SECTION X REGULAR IRREGULAR  
(NOTE: Locate Well on the Section Plat on Reverse Side  
County: Finney  
Lease Name: Anderson PX Well # 1-28  
Field Name: Amazon Ditch East

CONTRACTOR: License # 5658  
Name: Sweetman Drilling, Inc.

Is this a Prorated/Spaced Field? X yes no  
\*\* Target Formation(s): LKC

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Enh Rec ... Infield X Mud Rotary  
X Gas ... Storage X Pool Ext. ... Air Rotary  
... OWVO ... Disposal ... Wildcat ... Cable  
... Seismic: ... # of Holes ... Other

Nearest lease or unit boundary: 330'  
Ground Surface Elevation: 2950 Est. feet MSL  
Water well within one-quarter mile: X yes no  
Public water supply well within one mile: X yes no  
Depth to bottom of fresh water: 320-350'  
Depth to bottom of usable water: 1050-960'  
Surface Pipe by Alternate: X 1 2  
Length of Surface Pipe Planned to be set: 1700'  
Length of Conductor pipe required: 0'

If OWVO: old well information as follows:  
Operator:  
Well Name:  
Comp. Date: Old Total Depth

Projected Total Depth: 4850'  
Formation at Total Depth: St. Louis  
Water Source for Drilling Operations:  
X well ... farm pond ... other

Directional, Deviated or Horizontal wellbore? X yes no  
If yes, true vertical depth:  
Bottom Hole Location:

DWR Permit #: To be applied for  
Will Cores Be Taken?: X yes no  
If yes, proposed zone:

Exp. 12/13/95

AFFIDAVIT

980' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will

Pusher Eugene Salgado INIT. sm  
SPUD DATE 6-18-95  
LENGTH SURFACE PLANNED 1686  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 7/8 @ 1685 CONDUCTOR  
ANHYDRITE T-2000 B-2022 ELEVATION  
TD 4850 FORMATION  
RAN PIPE @ DV TOOL ALT II DONE  
SX Y N  
Arbuckle Plug @ Ft. W/ SX  
Hug./Council @ 3200 Ft. W/ 1000 SX  
Anhydrite Base @ 2022 Ft. W/ 50 SX  
1/2 Base Anyh. @ 40 Ft. W/ 1000 SX  
1/2, 1/2 Plug @ Ft. W/ SX  
Bottom Surface @ 1242 Ft. W/ 50 SX  
40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 65 SX MOUSE HOLE W/ 10 SX  
WATER WELL X (Irr. Well Pond  
Hauling  
TECHNICIAN DATE 6-26-95  
TYPE OF CEMENT 46-670  
STARTING TIME (AM/PM) DATE 6-27  
COMPLETION TIME 2:30 (AM/PM) DATE 6-28-95  
CEMENT COMPANY Hall

