

1090982

TO: STATE CORPORATION COMMISSION

12-18

API NUMBER 15-055-21,441-0000
NW SW NE SEC: 27, T 22 S, R 34 W

CONSERVATION DIVISION - PLUGGING SECTION 1630 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BOSWORTH WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY FINNEY 160.88

OPERATOR LICENSE # 5214

WELL TOTAL DEPTH 4950 FEET

OPERATOR: LARIO OIL & GAS CO.

PRODUCTION CSG: SIZE 5 1/2" @ 4950' WITH 250 SX

NAME AND 301 S MARKET

SURFACE CASING: SIZE 8 5/8" @ 1850' WITH 680 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 18 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4366-74, 4710-30

1ST PLUG SANDED BACK TO 4300' WITH 5 SX CEMENT, 2ND PLUG AT 2600' WITH 50 SX CEMENT,

3RD PLUG AT 1880' WITH 50 SX CEMENT, 8 SX GEL,

4TH PLUG AT 650' WITH 40 SX CEMENT,

5TH PLUG AT 40' WITH 25 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 2:45 PM DAY: 18 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SANDED BACK TO 4300' WITH 5 SX CEMENT, 2ND PLUG AT 2600' WITH 50 SX CEMENT,

3RD PLUG AT 1880' WITH 50 SX CEMENT 8 SX GEL, 12-23-98

4TH PLUG AT 650' WITH 40 SX CEMENT,

5TH PLUG AT 40' WITH 25 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2800' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID NOT) OBSERVE THIS PLUGGING.

SIGNED (TECHNICIAN) FORM CP-2/3

Handwritten signature

DEC 29 1998

60489