

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API-NUMBER 15-

SE, Sec. 25, T 16 S, R 11 W 1/4

825' feet from N/S section line

330 feet from N/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Bredford Well # 1

Operator: Viking Resources
Name & Address 217 E. William, Wichita, Ks.
67202

County Barton

Well Total Depth 3370 feet 109.53

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 276

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Logging Pulling License Number 6050

Address Box 176, Chase, Ks. 67524

Company to plug at: Hour: 10:00 AM Day: 21 Month: Dec. Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Neal Peddicord

(company name) Kelso Logging Pulling (phone) 316-938-2457

were: Order 16.5 sh. 50 permix - 4% sal. - 3% sal. ll., 15 sh. sal., 5 sh. bulbs & 8 5/8" plug.

Signed Gilbert G. Schulz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:55 PM Day: 30 Month: Dec. Year: 1983

ACTUAL PLUGGING REPORT 8 5/8" - 276' w/ 150 sh. 5 1/2" at 3360' w/ 100 sh.

10' of open hole. Plugged bottom w/ 5 sh. cement, sand & 5 sh. cement to 3300'. Shot pipe 2 times & recovered 2600'. Pumped in 8 5/8" - 4 sh. bulbs, 25 sh. cement, 12 sh. sal., 40 sh. cement, 3 sh. sal., 1 sh. bulb, released plug. & followed w/ 100 sh. cement w/ 900 pounds pressure.

Remarks: By Allied Cementing

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED STATE CORPORATION COMMISSION

JAN 16 1984 1-16-84

CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE 1-18-84

INV. NO. 9122TW

Signed Gilbert G. Schulz (TECHNICIAN)