

To: 1 090260 3-26
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-NA 15-055-20165-0000
NW SW, SEC. 26, T. 22 S, R. 31 W/R

TECHNICIAN'S PLUGGING REPORT

Operator License # 4779

1980 feet from S section line

4620 feet from E section line

Operator: North American Resources Company

Lease Name Stuckey Graber Well # 1

Name: 16 E. Granite

County Finney

Address Butte, MT 59701

Well Total Depth 2798 90.93 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 612

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor North American Resources Company License Number 4779

Address 16 E. Granite, Butte, MT 59701

Company to plug at: Hour: 11:15 a.m. Day: 26 Month: 3 Year: 1993

Plugging proposal received from Roger Pearson

(company name) NARCO (phone) 316-624-5636

were: 4 1/2" at 2797' w/675 sx cement, PBD 2761', Perfs at 2709-20'

Run tubing to 2558' and pump 15 bbl gel w/1 sx hulls and 75 sx cement,, circulate to surface,

Pull tubing to 1051', pump 50 sx cement, circulate to surface.

Check backside.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:45 p.m. Day: 26 Month: 3 Year: 1993

ACTUAL PLUGGING REPORT Ran tubing to 2558', pumped 15 bbl. gel, 1 sx hulls, and 75 sx cement.

Pulled tubing to 1051' and pumped 50 sx cement, circulated cement to surface.

Hooked onto backside, would not take cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 30 1993
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.

If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 3-31-93

Signed [Signature]
(TECHNICIAN)

WIL. NO. 37523
3-26