

To: 1 080064 15.055-26168-0001
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 055-20,168-A-0001

C NE, SEC. 32, T. 22 S, R. 31 W/X

3960 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Lease Name Lewis OWWO Well # 32-1

Operator: Kansas Corporation Commission

County Finney

Name: _____

Address _____

Well Total Depth 2740 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 348

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
never produced

Other well as hereinafter indicated _____

Plugging Contractor Kansas Corporation Commission License Number _____

Address _____

Company to plug at: Hour: 1 p.m. Day: 13 Month: 9 Year: 1996

Plugging proposal received from Richard Lacey

(company name) KCC (phone) 316-225-6760

was: 5 1/2" at 2739' w/475 sx cement, PBTD 2739', Perfs at 2701-11'

1st plug pump down 5 1/2" with 400 lbs. hulls and 342 sx cement,

2nd plug tie onto 8 5/8" X 5 1/2" annulus and pressure up to 500 psi with cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 13 Month: 9 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls, and 230 sx cement.

Maximum pressure 500 psi and shut in 500 psi.

RECEIVED
KANSAS CORP COM
1996 SEP 18 P 12 59

9-18-96

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Kenneth P. Strub
(TECHNICIAN)