

1-080194
TO:

S-14 API NUMBER 15-075-100040000

STATE CORPORATION COMMISSION C-SW-NE SEC 1, T 22 S, R 42 W
CONSERVATION DIVISION - PLUGGING SECTION 3300' FEET FROM SOUTH SECTION LINE
WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970' FEET FROM WEST SECTION LINE
WICHITA, KANSAS 67202 LEASE NAME COMBS GAS UNIT WELL# 1
TECHNICIAN'S PLUGGING REPORT COUNTY HAMILTON
OPERATOR LICENSE # 31409 WELL TOTAL DEPTH 2768' *89.96* FEET
OPERATOR: M.M. ENERGY INC. PRODUCTION CSG: SIZE 4 1/2 FEET 2766'
NAME AND 2601 N.W. EXPRESSWAY SURFACE CASING: SIZE 8 5/8 FEET 206'
ADDRESS SUITE, 904 EAST
OKLAHOMA CITY, OK 73112
ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A
OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER
ADDRESS P.O. BOX 31-24, RUSSELL, KS 67665-0031

COMPANY TO PLUG AT: HOUR: 9:00am DAY: 14 MONTH: 5 YEAR: 98

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) ROGER PEARSON (PHONE) (316)-624-5083

WERE: PERFS @ 2732'-34' 2738'-42' WELL SOUEEZED @ 950'-90' W/250 SX CEMENT, 1 1/4
TUBING FISH IN HOLE @2250' RUN PACKER IN HOLE TEST TO 300# SPOT 30 SX CEMENT THROUGH TUBING
ON TOP OF FISH, PERFORATE @ 1200' CEMENT W/CASING CAPACITY PLUS 80 SX, PUMP DOWN 8 5/8 BY 4
1/2 ANNULAS, 150 SX PLUGGING PROPOSAL RECEIVED BY Kevin Strube

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:00pm DAY: 14 MONTH: 5 YEAR: 98

ACTUAL PLUGGING REPORT 5-13-98 RAN TUBING TO 2210, ALLIED SPOTTED 30 SX CEMENT, TOP OF AT
1720; 5-14-98 PERFORATED AT 1200', ALLIED PRESSURED UP TO 500#, SLOW BLEED OFF TO 300#,
RAN TUBING IN HOLE TO 1210', ALLIED LOADED 4 1/2 WITH CEMENT, PULLED TUBING, PUMPED 103 SX
TOTAL DOWN 4 1/2, SHUT IN AT 600#, PUT 35 SX INTO FORMATION, WENT DOWN 8 5/8 X 4 1/2
ANNULAS, PUMPED TOTAL 150 SX CEMENT, SHUT IN 100#

REMARKS: Used 60/40 Pozmix 6% gel by ALLIED

No casing recovery

I (DID/xxxxxxx) OBSERVE THIS PLUGGING.

SIGNED *Kevin D Strube*
(TECHNICIAN)

RECEIVED
KANSAS CORP
MAY 21 A

5-21-98

INVOICED

MAY 26 1998

DATE

TRV. NO. 50603

5-14