

1080318

TO: STATE CORPORATION COMMISSION

API NUMBER 15-075-30,107-0000
E/2 SE NW SEC. 35, T 22 S, R 41 W

CONSERVATION DIVISION - PLUGGING SECTION 3300 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2790 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SHOUP WELL # 1-35

TECHNICIAN'S PLUGGING REPORT

6/14

COUNTY HAMILTON 86, 32

OPERATOR LICENSE # 32334

WELL TOTAL DEPTH 2656 FEET

OPERATOR: CHESAPEAKE OPERATING, INC. PRODUCTION CSG: SIZE 5 1/2" @ 2655' WITH 200 SX

NAME AND PO BOX 18496 SURFACE CASING: SIZE 8 5/8" @ 265' WITH 200 SX

ADDRESS OKLAHOMA CITY, OK 73154-0496

ABANDONED OIL WELL GAS WELL INPUT WELL RECEIVED SWD WELL D/A
STATE CORPORATION COMMISSION

OTHER WELL AS HEREINAFTER INDICATED

JUN 21 2000

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 31 RUSSELL, KS 67665 CONSERVATION DIVISION
Wichita, Kansas

COMPANY TO PLUG AT: HOUR: 11:15 AM DAY: 08 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DENNIS FRICK

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: PERFS AT 2632-33

ON 06/08/00 PUMPED BOTTOM WITH 400# HULLS AND 25 SX CEMENT. DISPLACED TO 2150'. SHUT IN WITH 500#. PERFORATED AT 1200'. ON 06/14/00 ALLIED CEMENTING PUMPED DOWN 5 1/2" CASING 185 SX. MAX PSI 700#. SHUT IN AT 300#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 200 SX CEMENT. MAX PSI 300#. SHUT IN AT 150#.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 12:40 PM DAY: 14 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT

ON 06/08/00 ALLIED PUMPED 400# HULLS AND 25 SX CEMENT DISPLACED TO 2150'. SHUT IN WITH 500#. PERFORATED AT 1200' BY LOG-TECH. ON 06/14/00 ALLIED CEMENTING PUMPED DOWN 5 1/2" CASING 185 SX CEMENT. MAXIMUM PSI 700#. SHUT IN AT 300#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 200 SX CEMENT. MAXIMUM PSI 300#, SHUT IN AT 150#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

DATE 6/27/00 SIGNED Kevin D. Strube (TECHNICIAN) FORM CP-2/3

RV. NO. 61900

