

1 031287

8-8

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-075-20,560-0000
NE SW SE, SEC. 31, T 22 S, R 41 W
850 feet from S section line
1850 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5236
Operator: Plains Resources, Inc.
Name & Address: 1600 Smith St.
Houston, TX 77002

Lease Name Dikeman Well # 1
County Hamilton 175.50
Well Total Depth 5400 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1125

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: 9 p.m. Day: 7 Month: 8 Year: 1994

Plugging proposal received from Gary Fisher

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2104-21'

1st plug at 2750' with 100 sx cement, 2nd plug at 2100' with 50 sx cement,

3rd plug at 1140' with 50 sx cement, 4th plug at 540' with 25 sx cement,

5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 1 a.m. Day: 8 Month: 8 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 2750' with 100 sx cement,

2nd plug at 2100' with 50 sx cement, 3rd plug at 1140' with 50 sx cement,

4th plug at 540' with 25 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 9-6-94

Signed Steve Durrant (TECHNICIAN)

INV. NO. 41112

8-8 NOV 16 1994

RECEIVED
STATE CORPORATION COMMISSION
AUG 11 1994
CONSERVATION DIVISION
WICHITA, KANSAS

EFFECTIVE DATE: 7-23-94

DISTRICT #

SEAL Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

State of Kansas

15

NOTICE OF INTENTION TO DRILL 075-20,560-0000

FORM MUST BE SIGNED ALL BLANKS MUST BE FILLED

Expected Spud Date 7 28 94 month day year

Spot NE SW SE Sec 31 Twp 22 S. Rg 41 East West

OPERATOR: License # 05236 Name: PLAINS RESOURCES, INC. Address: 1600 SMITH STREET City/State/Zip: HOUSTON, TX 77002 Contact Person: HERB SCHROEDER Phone: 713-654-1414

850' feet from South / North line of Section 1850' feet from East / West line of Section IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License # 30684 Name: ABERCROMBIE RTD, INC.

(NOTE: Locate well on the Section Plat on Reverse Side) County: HAMILTON Lease Name: DIKEMAN Well #: #1 Field Name: Is this a Prorated/Spaced Field? yes X no Target Formation(s): MISSISSIPPI Nearest lease or unit boundary: 790' Ground Surface Elevation: UNKNOWN Water well within one-quarter mile: yes X no Public water supply well within one mile: yes X no Depth to bottom of fresh water: 120' Depth to bottom of usable water: 1080' Surface Pipe by Alternate: X 1 2 Length of Surface Pipe Planned to be set: 1100' Length of Conductor pipe required: 0 Projected Total Depth: 5400' Formation at Total Depth: MISSISSIPPI Water Source for Drilling Operations: well farm pond X other DNR Permit #: WILL FILE Will Cores Be Taken? N/A yes X no If yes, proposed zone:

Well Drilled For: Well Class: Type Equipment: X Off Enh Rec Infield X Mud Rotary Gas Storage Pool Ext. Air Rotary OWD Disposal X Wildcat Cable Seismic: # of Holes Other If OWD: old well information as follows: Operator: N/A Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: N/A Bottom Hole Location:

Exp. 1/18/95

AFFIDAVIT

1100' Alt. I Req. RECEIVED STATE CORPORATION COMM.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will

Pusher Gary Fisher - Gary Fisher INIT. R.L.

SPUD DATE 7-23-94 LENGTH SURFACE PLANNED 1100 OF 850 RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 5/8 @ 1125 CONDUCTOR ANHYDRITE T- 2104 B- 2121 ELEVATION

TD 5400 FORMATION RAN PIPE @ DV TOOL ALT II DONE SX Y N

Arbuckle Plug @ 2750 Ft. W/ SX Hug./Council @ Kridler Ft. W/ 100 SX

Anhydrite Base @ 2100 Ft. W/ 50 SX 1/2 Base Anyh. @ 1140 Ft. W/ 50 SX

1/2, 1/2 Plug @ 540 Ft. W/ 25 SX Bottom Surface @ Ft. W/ SX

40' Plug @ 40-0 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 12 SX

WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN SD DATE 8-4-94

TYPE OF CEMENT 6040 6 1/2 bbls STARTING TIME DATE 8-7-94

COMPLETION TIME DATE 8-8-94 CEMENT COMPANY

STATE CORPORATION COMMISSION RECEIVED AUG 10 1994 CONSERVATION DIVISION WICHITA, KANSAS