

TO: STATE CORPORATION COMMISSION

API NUMBER 15-055-21,643-0000
SW NE NE SEC. 2, T 22 S, R 33 W

CONSERVATION DIVISION - PLUGGING SECTION 1250 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1250 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME CORRIGAN WELL # 1-2

TECHNICIAN'S PLUGGING REPORT COUNTY FINNEY

OPERATOR LICENSE # 32166 WELL TOTAL DEPTH 2872 FEET

OPERATOR: DUNNE EQUITIES OPERATING, INC. PRODUCTION CSG: SIZE 5 1/2" @ 2872' WITH 265 SX

NAME AND 8100 E 22ND ST NORTH #1100 SURFACE CASING: SIZE 8 5/8" @ 318' WITH 220 SX

ADDRESS WICHITA, KS 67226-2311

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT. 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 20 MONTH: 03 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC (PHONE) 580-854-6515

WERE: PERFS AT 2626-34

PUMPED DOWN 5 1/2" 200# HULLS WITH 25 SX COMMON CEMENT. LOADED HOLE WITH DRILLING MUD.

PRESSURE UP TO 1000#. PULLED CASING TO 770' PUMPED 40 SX CEMENT. PULLED TO 340' PUMPED

40 SX CEMENT. PULLED TO 40' PUMPED 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 5:30 PM DAY: 20 MONTH: 03 YEAR: 2000

ACTUAL PLUGGING REPORT _____

PUMPED DOWN 5 1/2" 200# HULLS WITH 25 SX COMMON CEMENT. LOADED HOLE WITH DRILLING MUD.

PRESSURE UP TO 1000#. PULLED CASING TO 770' PUMPED 40 SX CEMENT. PULLED TO 340' PUMPED

40 SX CEMENT. PULLED TO 40' PUMPED 10 SX CEMENT.

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 801' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin D. Strube
(TECHNICIAN) FORM CP-2/3