

To: 6 070699
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT
Operator License # 6883

Operator: Robinowitz Oil Company
Name & Address 7310 S. Lewis #910
Tulsa, Ok. 74136

Abandoned Oil Well _____ Gas Well _____ Input Well x SWD Well _____ O&A _____

Other well as hereinafter indicated _____
Plugging Contractor B. J. Titan License Number _____
Address Great Bend, Ks. 67530

Company to plug at: Hour: 10:00 AM Day: 18 Month: July Year: 19 88

Plugging proposal received from Don Degenhardt
(company name) Robinowitz Oil Company (phone) _____

were: 8 5/8" 747' S.P. cwc w/350 sks cement, 5 1/2" casing. Set at 3255' w/125 sks
Perfs at 2865' - 2965'. No casing recovery. Tubing fish at 1705'. Proposal 50 sks

Class A Cement and 350 sks 65/35 Poz 10% Gel 2% Additive. Open annulus with pump truck load both 5 1/2" casing and 5 1/2" and 8 5/8" annulus with cement. Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Operations attended by Agent?: All x Part _____ None _____
Hour: 3:45PM Day: 18 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Ordered 50 sks Class A Cement and 350 sks 65/35 Poz 10% Gel 2% Additive w/1/2 lb. F.C. per sk. Pumped in with pump truck annulus open. 1. Pumped in 50 sks Common and 350 sks 65/35 Poz 10% Gel. Had circulation. 2. Returned for another 300 sks 65/35 Poz 10% Gel Pumped in 5 1/2" casing. 3. On July 19, 1988 tagged cement in 5 1/2" casing at 200'. Filled w/15 sks cement. Squeezed annulus w/75 sks cement. 310 Psig. Max pressure shut in at 300 psig. Total cement 790 sks.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-26-88
INV. NO. 22726

API NUMBER 15- 1953
S/2 N/2
NW _____, SEC. 31, T 16 S, R 11 W/EX
990 4290 FSL feet from N section line
1320 3960 FEL feet from E section line
Lease Name Zorn Well # 6
County Barton 106.70
Well Total Depth 3283 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 747

AMB
KCC

7-18 15-009-03158-0001

Signed Marion J. Schmidt
Marion J. Schmidt (TECHNICIAN)

D