

6 061908

7-18

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 009-23,510 0000
NE, SEC. 31, T 16 S, R 11 W/E
3630 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5501

Lease Name Ogden Well # 1

Operator: Raymond M. Goodin Trust

County Barton 108.29

Name & Address 333 E English

Well Total Depth 3332 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 744

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 11:00 AM Day: 18 Month: July Year: 19 89

Plugging proposal received from Mallard Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

were: Order 200 sks 60/40 poz 8% gel 5 sks hulls.

RECEIVED
STATE CORPORATION COMMISSION

08-11-89 AUG 11 1989

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:10PM Day: 18 Month: July Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 744' w/375 sks. 5 1/2" set at 3332' w/

160 sks. Top perf at 2988'. Plugged bottom w/sand and 5 sks cement to 2925'. Shot pipe two times and recovered 2300'. Pumped in 8 5/8" 25 sks cement followed w/5 sks hulls in 175 sks cement w/975 psi.

Remarks: By Halliburton
(if additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

INVOICED

Signed *Gilbert G. Scheck*
(TECHNICIAN)
Gilbert G. Scheck

DATE 8-16-89

INV. NO. 25617