

8-18-88

To: 6 061574  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-009-15079-0000  
NE 31, SEC. 16, T. 11 S, R. W/EX  
4290 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565  
Operator: National Cooperative  
Name & Address Refinery Association  
Box 6  
Great Bend, Ks. 67530

Lease Name Valenta Well # 6  
County Barton 108.25  
Well Total Depth 3346 feet  
Conductor Pipe: Size        feet  
Surface Casing: Size 8 5/8 feet 750

Abandoned Oil Well  Gas Well  Input Well  SWD Well  U&A

Other well as hereinafter indicated       

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 10:00AM Day: 18 Month: Aug Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2457

were: Order 200 sks 60/40 Poz 8% Gel 3% Cal Cl 5 sks Hulls.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 30 1988

08-30-88

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:00AM Day: 18 Month: August Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 750' w/400 sks. 5 1/2" set at 3344' w/125 sks.

Top perf at 2983'. Plugged bottom w/sand and 5 sks cement to 2900'. Shot pipe

four times and recovered 2100'. Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 175 sks cement w/600 Psi.

Remarks: By Allied.

(If additional description is necessary, use BACK of this form.)

**INVOLVED**  
I hereby agree to observe this plugging.

DATE 8-31-88

Signed Gilbert G. Scheck  
(TECHNICIAN)  
Gilbert G. Scheck

D

INV. NO. 72070