

1 110014

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,231-0000

NW NE SW, SEC. 21, T 22 S, R 25

2310 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161

Operator: Palomino Petroleum
Named
Address P. O. Box 18610
Wichita, KS 67218

Lease Name Potter Trust Well # 1

County Hodgeman

Well Total Depth 4734 Mississippi 153' 46" feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor DNB Drilling, Inc. License Number 5476

Address 535 North Oliver, Wichita, KS 67208

Company to plug at: Hour: 3:30 pm Day: 19 Month: December Year: 19 85

Plugging proposal received from Jack Taylor

(company name) DNB (phone) 316-687-5471

Elevation 2534 GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1730'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 1/2 the Anhydrite plus 50' with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by James R. Kapp

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 pm Day: 19 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1730' with 50 sx cement, 2nd plug at 1330' with 80 sx cement, 3rd plug at 280' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement,

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging

INVOICED

STATE CORPORATION COMMISSION

12-27-85

James R. Kapp
(TECHNICIAN)

DATE DEC 27 1985

DEC 27 1985

INV. NO. 11751 12-19

CONSERVATION DIVISION

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 12 9 85 month day year

API Number 15- 083-21,231-0000

OPERATOR: License # 5161 Name Palomino Petroleum Address P.O. Box 18610 City/State/Zip Wichita, KS 67218 Contact Person Bob Watchous Phone (316) 683-8152

NW NE SW Sec. 21 Twp. 22 S. Rg. 25 XX East West 2310 3630 Ft. from South Line of Section Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5476 Name DNB Drilling, Inc. City/State Wichita, KS

Nearest lease or unit boundary line 330 feet County Hodgeman Lease Name Potter Trust Well # 1 Ground surface elevation 2534 feet MSL

Well Drilled For: X Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Surface pipe by Alternate: 1 2 X Depth to bottom of fresh water 100 Depth to bottom of usable water 600 Surface pipe planned to be set 240+ Projected Total Depth 4700 feet Formation Miss.

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. X cementing will be done immediately upon setting production casing Date 12-2-85 Signature of Operator or Agent Bob Watchous Title Owner

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. 2 This Authorization Expires 6-3-86 Approved By 12-3-85

Handwritten notes: 240 + 85/8, 1 Base ends 50m, 2 1/2 Aug + 150' 80m, 3 Bottoms SP + 30' - 40 ext, 4 40' SBP, 104 hours 10m, Mouse Circulate 10m

RECEIVED STATE CORPORATION COMMISSION

DEC 27 1985

Handwritten signatures: Pauline Water, Allie's Company

CONSERVATION DIVISION Wichita, Kansas