


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



KINGMAN County, Sec. 17 Twp. 30 Rge. 9 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW SW NW
Lease Owner PETROLEUM, INC.,
Lease Name DEPENBUSCH UNIT Well No. 1
Office Address R.R. #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed Nov. 1 19 65
Application for plugging filed Nov. 10 19 65
Application for plugging approved Nov. 12 19 65
Plugging commenced Nov. 13 19 65
Plugging completed Nov. 17 19 65
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONE

If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING
Producing formation _____ Depth to top 4332 Bottom 4385 Total Depth of Well 4441 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-------------|------------------------|------|------|--------|--------|------------|
| MISSISSIPPI | | 4336 | 4350 | 8-5/8 | 213' | NONE |
| | SLIGHT AMOUNT OF WATER | | | 5 1/2" | 4436' | 1456' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED BACK TOTAL DEPTH 4385'

DUMPED 100 GALS. SAND AND PUMPED PLUG ON TOP OF SAND TO 4285', MIXED AND RAN 5 SACKS CEMENT ON TOP OF PLUG. MUDDED HOLE TO 210', SET 10' ROCK BRIDGE, MIXED AND RAN 25 SACKS CEMENT THRU DUMP BAILER. MUDDED HOLE TO 40', SET 10' ROCK BRIDGE, MIXED AND DUMPED 10 SACKS CEMENT ON TOP OF PLUG TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1965
11-29-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SOUTHWEST CASING PULLING CO. INC.,
Address Box 364, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (XXXXXX XXXXXX) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.
(Signature) *Monte Chadd*
ROUTE #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 23 day of NOVEMBER, 19 65

My commission expires MAY 28, 1969

Richard N. Dumber
Notary Public.

WELL LOG ^{PC}_{gf.}

15-095-30119-0000

COMPANY Petroleum, Inc.
FARM Depenbusch Unit NO. 1


SEC. 17 T. 30S R. 9W
LOC. NW SW NW

TOTAL DEPTH 4441'

COUNTY Kingman

COMM. 9-30-65 COMP. 10-13-65

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 213' w/200 sx
5 1/2" @ 4436' w/125 sx

ELEVATION 1711' KB

PRODUCTION Mississippi

FIGURES INDICATE BOTTOM OF FORMATIONS

- 110' Sand
- 213' Shale and Red Bed
- 300' Red Bed
- 1270' Red Bed and Shale
- 1480' Shale
- 1680' Shale and Lime Streaks
- 2005' Lime
- 2245' Lime and Shale
- 2505' Shale and Lime
- 2550' Sand
- 2600' Shale and Lime
- 2710' Shale and Lime Streaks
- 3156' Shale and Lime
- 3220' Lime and Shale
- 3315' Shale
- 3580' Shale and Lime
- 3607' Shale
- 3681' Douglas Sand
- 3697' Shale and Lime
- 4224' Lime
- 4350' Lime and Shale
- 4365' Lime and Chert
- 4405' Chert
- 4430' Chert and Lime
- 4441' Lime
- 4441' RTD

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1965
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Depenbusch #1 well.

Sam N. Stephens

Subscribed and sworn to before me this 26th day of October 19 65

My Commission Expires: May 28, 1969

Richard A. Dumber
NOTARY PUBLIC