

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

KINGMAN County, Sec. 23 Twp. 30s Rge. 9 (R) (W)

Location as "NE/CNW/SW" or footage from lines SE NE SW
Lease Owner PETROLEUM, INC.
Lease Name DEPENBUSCH "F" Well No. 1
Office Address ROUTE #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed AUGUST 10 19 66
Application for plugging filed AUGUST 10 19 66
Application for plugging approved AUGUST 10 19 66
Plugging commenced AUGUST 10 19 66
Plugging completed AUGUST 10 19 66
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONE

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING
Producing formation - Depth to top - Bottom - Total Depth of Well 4310 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	206'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 200', 1 SACK DRY CEMENT, FOLLOWED BY WOODEN PLUG,
PLACED 1/2 SACK HULLS, 24 SACKS CEMENT ON TOP OF PLUG. MUDDED UP WITH HEAVY MUD
TO 40', 1 SACK DRY CEMENT, FOLLOWED BY WOODEN PLUG, PLACED 1/2 SACK HULLS, 9
SACKS CEMENT ON TOP OF PLUG TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1966
8-25-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING CO.
Address R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD, DIST. PROD. SUPT. (employee of owner) or (owner operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) *Monte Chadd*

ROUTE #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of AUGUST, 19 66

My commission expires MAY 28, 1969.

Richard H. Tomules
Notary Public.

WELL LOG

COMPANY Petroleum, Inc.

SEC. 23 T. 30S R. 9W

FARM Depenbusch

NO. F-1

LOC. SE NE SW


TOTAL DEPTH 4310'

COUNTY Kingman

COMM. 8-1-66

COMP. 8-10-66

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 206' w/250 sx

ELEVATION 1601' KB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 40' Surface Sand and Clay
- 206' Red Bed
- 1435' Shale and Shells
- 2190' Lime and Shale
- 2955' Shale and Lime
- 3535' Lime and Shale
- 3665' Shale and Lime
- 4045' Lime
- 4258' Lime and Shale
- 4273' Mississippi Chert
- 4293' Chert
- 4310' Lime
- 4310' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 25 1966
 CONSERVATION DIVISION
 WASHINGTON, KANSAS

State of Kansas }
 County of Barton } 89

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Depenbusch F-1 well.

Sam N. Stephens

Subscribed and sworn to before me this 23rd day of August 1966

My Commission Expires: November 5, 1969

Richard Boys
 NOTARY PUBLIC