


15-155-20111-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



_____ Reno County, Sec. 14 Twp. 23 Rge. 10 (E) _____ (W)
Location as "NE/CNW/SW" or footage from lines 150'N 100W NE/4
Lease Owner Braden Deem, Inc.
Lease Name Lang #1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 5/5/71 _____ 19____
Plugging completed: 6/18/71 _____ 19____
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3770 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	252	none
				7"	3760'	2712'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran sand to 3750', ran 6 sacks of cement. Loaded hole with water, shot pipe at 2980', 2830', 2710', worked pipe loose and pulled 87 joints. Pumped 2 sacks hulls, 10 sacks mud and 100 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1971
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor _____
Address _____
(If additional description is necessary, use BACK of this sheet)
KNIGHT CASING PULLING CO., INC.
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of June, 19 71

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

15-155-20111-0000

DRILLERS LOG

#1 LANG
150' N & 100' W of C NE
Section 14-23S-10W
Reno County, Kansas

OPERATOR: Braden-Deem, Inc.
210 One Twenty Building
Wichita, Kansas

CONTRACTOR: Dunne-Gardner Petroleum, Inc.
300 Schwelter Building
Wichita, Kansas

COMMENCED: May 9, 1969

COMPLETED: May 17, 1969

CASING RECORD: 10-3/4" @ 252' w/500 sx
7" @ 3760' w/100 sx

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1971
CONSERVATION DIVISION
Wichita, Kansas

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	252	Sand, clay & shale
252	985	Red bed & shale
985	1315	Shale
1315	1515	Lime & shale streaks
1515	1921	Lime & shale
1921	2165	Broken lime
2165	2580	Lime and shale
2580	3667	Lime
3667	3724	Cherty lime & shale
3724	3758	Lime
3758	3760	Lime & chert
3760		Rotary Total Depth

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

DUNNE-GARDNER PETROLEUM, INC.


Don Gardner

Subscribed and sworn to before me this 19th day of May, 1969.

My commission expires:
December 14, 1969


Notary Public