


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
806 Bittig Building
Wichita, Kansas

Reno County, Sec. 14 Twp. 23S Rge. 10W(E) (W)

E 23s NORTH E 10w



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines CNW SE
Lease Owner West Supply Co., Inc.
Lease Name C. C. Crandall Well No. 1
Office Address Chase, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil well
Date well completed July 27 1942
Application for plugging filed September 15 1955
Application for plugging approved September 16 1955
Plugging commenced September 29 1955
Plugging completed October 5 1955
Reason for abandonment of well or producing formation Ceased production.

If a producing well is abandoned, date of last production August 1955
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3867 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	290'	None
				5-1/2"	3762'	2910'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled the hole with sand from 3767' to 3750' and ran 6 sacks of cement. Mudded the hole to 260', set a 10' rock bridge and ran 15 sacks of cement. Mudded the hole to the top and ran 5 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss. Noel J. Knight (~~employee of owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5th. day of October, 1955

Edward E. O'Brien
Edward E. O'Brien Notary Public.

My commission expires May 20, 1957

PLUGGING
FILE SEC 14 T3 R10W
BOOK PAGE 150 LINE 14

RECEIVED
STATE CORPORATION COMMISSION

OCT 7 - 1955 10-7-55
CONSERVATION DIVISION
Wichita, Kansas

SINCLAIR PRAIRIE OIL CO.
Cecil C. Grandall No. 1

SEC. 14 T. 23 R. 10 W
C4W SE
638' f N&W lines NW 1/4 SE 1/4


County Reno.

Total Depth. 3767
Comm. 7-12-42 Comp. 7-27-42
Shot or Treated.
Contractor. Harbar Drilling Co.
Issued. 9-5-42

Rotary

CASING.

8 5/8" 290'
5 1/2" 3762'



Elevation.

B.H.B.

Production Pot. 5435 B.

Figures Indicate Bottom of Formations. for Max. Pot. 3000 B.

no wtr.

sand	123
red bed and shale	860
shale and shells	1050
salt and shale	1220
shale	1395
shale and shells	1400
lime and shale	1505
shale	1620
lime and shale	1692
sand and lime	1765
shale and lime	2265
lime broken	2490
shale and lime	2580
lime broken	2705
lime and shale	2805
lime	3010
shale and lime	3210
shale	3280
shale and lime	
chert	3330
shale and lime	3410
shale and lime	
chert	3450
shale and lime	3565
lime and chert	3600
chert	3630
lime	3640
shale	3760
lime	3767

Total Depth.

All Meas. corrected to Rig floor.

Top Viola 3760

Good oil show 3762-65

Oil fillup 200' first 30 min, 1100' next 30 min, Total 1300' first hr.

Total 3000' in 2 hours.

Temporary test 8-3-42 Potential 125 bbls.,

Acidized 8-7-42 with 300 gal.

Test following with bottom hole bomb, made 5435 bbls oil

for a Max. pot. of 3000 oil no water 8-10-42

RECEIVED
STATE CORPORATION COMMISSION
OCT 6 - 1955
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1955

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 14 T 23 R 10W
BOOK PAGE 50 LINE 14

Duck