

15-155-02208-0800

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Reno County, Sec. 14 Twp. 23 Rge. 10 (E) W (W)
 Location as "NE/CNW/SW" or footage from lines 660' N. & 660' E. of Cen.
 Lease Owner Cities Service Oil Company
 Lease Name Sentney Well No. 3
 Office Address Box 144, Great Bend, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Oil well
 Date well completed June 28 19 42
 Application for plugging filed January 29 19 59
 Application for plugging approved January 30 19 59
 Plugging commenced February 2 19 59
 Plugging completed February 11 19 59
 Reason for abandonment of well or producing formation Depleted formation

If a producing well is abandoned, date of last production October 15 19 59
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hempel
 Producing formation Viola Depth to top 3744 Bottom 3762 Total Depth of Well 3762 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	257'	None
				5-1/2"	3751'	1628'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3762-3730', river sand.
3730-3690', 5 sacks cement.
3690-240', heavy mud.
240-165', rock bridge and 20 sacks cement.
165-35', heavy mud.
35' to base of cellar, rock bridge and 10 sacks cement.

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 17 1959
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor C. E. Shull Casing Pulling Company
 Address Box 558, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. M. Conover (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. M. Conover
Box 144, Great Bend, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of February, 19 59

My commission expires March 12, 1959 Notary Public.

PLUGGING
 FILE SEC 14 T. 23 R. 10
 BOOK PAGE 13 LINE 44

WELL RECORD

15-155-02208-0000

Company Cities Service Oil Co. Well No. 3 Farm Sontney
 Location 660' north and 660' east of Center Sec. 14 T. 23 R. 10W
 Elevation 1755 County Reno State Kansas
 Drlg. Comm. June 11, 1942 Contractor Hissom Drilling Company
 Drlg. Comp. June 28, 1942 Acid 500 gals. July 3, 1942
 T. D. 3762' Initial Prod. B. H. P. Gauge Potential: 3000 oil, no water, 24 hours
 (Ind. Cap. Infinite)

CASING RECORD:

6-5/8" @ 257' con. 200 ex Atlas and
 2 ex C. C.
 5-1/2" @ 3751' con. 75 ex Monarch

FORMATION RECORD:

surface clay 0-45
 sand 65
 red bed & shells 257
 shale & shells 1024
 shale & salt 1235
 salt, shale & shells 1305
 anhydrite and lime 1475
 sand & lime 1575
 shale & lime broken 1700
 shale & lime 1760
 lime 1846
 lime & shale 2030
 shale & lime broken 2237
 shale & lime 2450
 shale 2491
 lime 2560
 shale 2572
 shale & lime broken 2741
 broken lime 2756
 shale & lime 2855
 lime 2958
 shale & lime 3104
 shale 3155
 shale hard 3220
 shale 3275
 lime 3440
 lime & shale 3585
 lime 3603
 cherty lime & shale 3620
 lime & shale 3717
 shale 3720
 cherty lime 3760
 lime 3764

3764, Rot. TD = 3760 SLM
 dolomite and chert 3762 T. D.

Corr. Top Viola 3744'
 Penetration 18'
 Total Depth 3762'

Loaded hole with 1700' water before drilling-in.

Hole filled 600' (1700' to 2500') in 30 minutes.

Syfo: 500' 0°
 1000' 0°
 1500' 0°
 2000' 0°
 2500' 0°
 3000' 0°
 3500' 0°

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 30 1953
 CONSERVATION DIVISION
 WICHITA, KAN.

PLUGGING
 FILE SEC. 14 T. 23 R. 10W
 BOOK PAGE 13 LINE 44