

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-19842-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 14-32S-10E  
1627 feet from S Section Line, 2283 feet from E Section Line  
Lease Name: SHAFFER B Well #: 6  
County: CHAUTAUQUA Total Vertical Depth: 2078 feet

Operator License No.: 30252  
Op Name: PATTESON OIL, A GENERAL PARTNER  
Address: PO BOX 177  
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5	1980		0 SX
SURF	10	681		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: DUANE SIMS Company: \_\_\_\_\_ Phone: (620) 725-5695

Proposed  
Plugging  
Method:

Run 1" to bottom - Cement 5 sacks Run 1" to middle - Cement 5 sacks Run 1" to 550' - Cement to surface

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/15/2016 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1950' gelled hole and spotted 15 sack plug. Pulled 1" and perforated casing at 1000' and 550'. Ran 1" to 1000' and spotted 25 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 234 sacks of cement were used to plug this well.

RECEIVED  
KCC DIST # 3  
OCT 18 2016  
CHANUTE, KS

DS

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST SENT OUT BY THE KCC

Plugged through: TBG

District: 03

Signed

*D. Sims*

(TECHNICIAN)

KCC WICHITA  
OCT 21 2016  
RECEIVED

10-21-16

NOV 02 2016

*No*