

To: 1 09.2224 10-27  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 15-055-10022-0000322  
Spudded 10/18/60

C SW NW, SEC. 27, T. 22 S, R 33 W/E  
3300 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6417  
Operator: Union Pacific Resources Co.  
Name:  
Address: P.O.Box 7, MS 3407  
Fort Worth, TX 76101-0007

Lease Name Sooby Well # 2  
County Finney 55.84  
Well Total Depth 4795 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 402

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Union Pacific Resources Co. License Number 6417  
Address P.O. Box 7, MS 3407, Fort Worth, TX 76101-0007

Company to plug at: Hour: 10 a.m. Day: 27 Month: 10 Year: 19 92

Plugging proposal received from Roy Case  
(company name) Union Pacific Resources (phone) 817-877-6000

were: 7" at 4795' w/550 sx cement. PRTD 4570'. Perfs at 4416-48, 4675-85, 4734-44'  
1st plug set CIBP at 4570',  
2nd plug fill with mud and pump 40 sx cement at 2000',  
3rd plug pump 40' sx cement at 1100',  
4th plug pump fill 500-0', 5th plug pump 100sx cement down 10 3/4" X 7" annulus.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 3:15 p.m. Day: 27 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set cement retainer at 4386' and pumped 40 sx cement,  
2nd plug ran in with tubing to 2000' and pumped 40 sx cement, loaded with mud,  
3rd plug pulled to 1090' and circulated cement to surface.  
Hooked onto backside-500 lbs. instant pressure.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.  
(If additional description is necessary, use BACK of this form.)  
OCT 29 1992

INVOICED  
DATE 11-16-92  
INV. NO. 36763

Signed \_\_\_\_\_  
(TECHNICIAN)