

To: 100142
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

7-3

15-055-10021-0000

API NUMBER 15- Drilled 4/20/56

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210

Operator: Lebsack Oil Production

Name & Address P.O. Box 489

Hays, KS 67601-0489

NW NW NW, SEC. 27, T 22 S, R 33 W/E

4950 feet from S section line

4950 feet from E section line

Lease Name Sooby Well # 1

County Finney 15S, 25

Well Total Depth 4777 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 347

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage License Number 31529

Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 3 Month: 7 Year: 19 97

Plugging proposal received from Manny Boatwright

(company name) Mike's Testing & Salvage (phone) 316-938-2943

Work: 5 1/2" at 4776' w/350 sx cement, CIBP 4750', Perfs at 4728-40'

1st plug sand back to 4675' and dump 5 sx cement on top of sand through bailer,

2nd plug at 1200' with 80 sx cement, 3rd plug at cut off with 50 sx cement,

4th plug at 380' with 90 sx cement, 5th plug at 40' with 20 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 3 Month: 7 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4654' and dumped 5 sx cement on top of sand through bailer,

2nd plug spotted 15 sx gel ahead of 80 sx cement at 1180',

3rd plug spotted 30 sx cement at 700',

4th plug spotted 90 sx cement at 380',

5th plug spotted 20 sx cement at 40-0'.

Remarks: Used 65/35 Pozmix 6% gel by Allied. Recovered 1200' of 5 1/2" casing

(If additional description is necessary, use BACK of this form.)

I (do ~~not~~) observe this plugging.

DATE JUL 16 1997

WV. NO. 485-86

Signed Gary Winters
(TECHNICIAN)

7-10-97

RECEIVED
1997 JUL 10 A.M.
KANSAS CORP. COM.