

1 060015

12-15-89

15.055.10611.0001

To:

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Docket #D-15,861

## TECHNICIAN'S PLUGGING REPORT

Operator License # 6417

Operator: Union Pacific Resources Company

Name &amp; Address P.O. Box 7 - MS 3407

Fort Worth, TX 76101-0007

SE SE SW, SEC. 27, T 22 S, R 33 W/E

330 feet from S section line

2970 feet from E section line

Lease Name Adams SWD Well # 1

County Finney

159.15

Well Total Depth 4897 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 352

Abandoned Oil Well Gas Well Input Well SWD Well X O&amp;A

Other well as hereinafter indicated

Plugging Contractor Union Pacific Resources Company License Number 6417

Address P.O. Box 7, MS 3407, Fort Worth, TX 76101-0007

Company to plug at: Hour: 11:50 a.m. Day: 15 Month: 12 Year: 19 89

Plugging proposal received from Ed Wallace

(company name) Union Pacific Resources Company (phone) 316-275-9547

were: 7" at 4896' PBSD 4110' Perfs at 4258-68' Squeezed from 1098-1029' Bridge Plug at 1500'

Pump through tubing:

1st plug pump 50 sx cement at 980', gel from 700-350',

2nd plug pump 65 sx cement from 380-0'.

3rd plug pump 50 sx cement down backside.

Plugging Proposal Received by Richard Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:45 p.m. Day: 15 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug spotted 50 sx cement through tubing at 980', gel from 700-350',

2nd plug pumped 65 sx cement from 380-0'.

3rd plug pumped 50 sx cement down annulus, cement circulated.

Remarks: Used 65/35, 1000 cement by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICE

DATE MAR 13 1990

INV. NO. 27627

Signed Can M... (TECHNICIAN)