

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21168-00-00
Spot: SESESW Sec/Twnshp/Rge: 29-22S-33W
330 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: SRAJER Well Number: 1-29
County: FINNEY Total Vertical Depth: 4980 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 1746 WITH 745 SX CMT
Production: Size 4.5 feet: 4979 WITH 525 SX CMT
Liner: Size feet: 9161.85

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/20/2001 10:45 AM
Plug Co. License No.: 6547 Plug Co. Name: SARGENTS CASING PULLING SERVICE
Proposal Rcvd. from: DON HORTON Company: SARGENTS CASING PULLING SER Phone: (316) 624-7455

Proposed Plugging Method: CIBP @ 4700' 2 SX CMT ON TOP. CIBP @ 3000' WITH 2 SX CMT ON TOP. PRESSURE TEST. 1ST PLUG AT 1770' WITH 40 SX CMT. 2ND PLUG AT 900' WITH 30 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/20/2001 2:30 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

CIBP @ 4785'. PERFS AT 4824-28, 4802-07, 4734-44'. SQUEEZED PERF AT 4305-10'. SET CIBP @ 4700' WITH 2 SX CMT ON TOP. SET CIBP @ 3000' WITH 2 SX CMT ON TOP. PRESSURE TESTED TO 500# AND HELD FOR 30 MINUTES. 1ST PLUG PULLED UP TO 1770' & PUMPED 40 SX CMT. 2ND PLUG PULLED UP TO 900' & PUMPED 30 SX CMT. 3RD PLUG PULLED TO 40' AND PUMPED 10 SX CMT.

Remarks: USED COMMON CMT BY SARGENTS. RECOVERED 1822' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

9-25-01
RECEIVED

SEP 25 2001

KCC WICHITA

Signed

Kevin D Strube

(TECHNICIAN)

INVOICED

SEP 24 2001

DATE

9-25-01

INV. NO.

2002060618

Form CT-213