

To: 1 031231  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-9

API NUMBER 15-

15-055-20473-0001  
D-24,017

NW NW SE NE, SEC. 10, T 22 S, R 34 W, EX

3910 feet from S section line  
1270 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7217

Lease Name Goering Well # 1

Operator: Brady Fluid Service Inc.

County Finney

Name:

Address P O BOX 94

Well Total Depth 3149 102.34 feet

Garden City, KS 67846

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 287

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Post & Mastin Well Service, Inc. License Number 8438

Address P.O. Box 297, Garden City, KS 67846

Company to plug at: Hour: 10:30 a.m. Day: 8 Month: 6 Year: 19 93

Plugging proposal received from Keith Brady

(company name) Brady Fluid Service Inc. (phone) 316-275-5827

work: 4 1/2" at 3149' w/825 sx cement, PBTD 2500', Perfs at 1580-1710', holes in casing @ 1390-1440

1st plug sand back to 1580' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 150 sx cement down 4 1/2" and shut in, 3rd plug pump 50 sx cement,

4th plug tag cement and fill to surface.

Check 4 1/2" X 8 5/8" annulus.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 9 a.m. Day: 9 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 1580' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 150 sx cement down 4 1/2" and shut in, waited 4 hours,

3rd plug pumped another 50 sx cement and shut down over night,

4th plug tagged cement at 400', filled to surface with 25 sx cement.

Checked 4 1/2" X 8 5/8" annulus to 500#-OK. Several attempts were made by the operator to squeeze the hole at 1390-1440'. Would not hold squeeze when drilled out.

Remarks: No casing recovery. Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / xxxxxxxx) observe this plugging.

DATE 6-15-93

Signed Steve Durrant (TECHNICIAN)

INV. NO. 37924