

1090966

TO: STATE CORPORATION COMMISSION

10-30

API NUMBER 15-055-21,610-0000
NW SE SE SEC. 20, T 22 S, R 34 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BARRETT WELL # 20-5

TECHNICIAN'S PLUGGING REPORT

COUNTY FINNEY 157.63

OPERATOR LICENSE # 31594

WELL TOTAL DEPTH 4850 FEET

OPERATOR: SONAT EXPLORATION COMPANY PRODUCTION CSG: SIZE 5 1/2" @ 4680' WITH 620 SX

NAME AND 14000 QUAIL SPRINGS PKWY #100 SURFACE CASING: SIZE 8 5/8" @ 1819' WITH 700 SX

ADDRESS OKLAHOMA CITY, OK 73134

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR HALLIBURTON ENERGY SERVICES LICENSE NUMBER NA

ADDRESS 200 E 1ST, STE 502, FARMERS & BANKERS BLDG. WICHITA, KS 67202-1823

COMPANY TO PLUG AT: HOUR: 10:15 AM DAY: 30 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKE PROCTER

(COMPANY NAME) HALLIBURTON (PHONE) 405-749-5337

WERE: PERFS AT 4011-15

LOAD CASING WITH MUD, PERFORATE 5 1/2" CASING 50' BELOW 8 5/8" SURFACE CASING. FILL 5 1/2" CASING AND 5 1/2" ANNULAS FROM 1869' TO 5' BELOW GL WITH 668 CUBIC FEET OF 60/40 POZMIX 8% GEL.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:40 AM DAY: 30 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 3970' WITH 25 SX CEMENT ON TOP. 11-3-98

2ND PLUG PERFORATE CASING AT 1870'. LOAD HOLE WITH MUD. HALLIBURTON PUMPED IN 365 SX CEMENT. CIRCULATED 2 BBL TO PIT.

REMARKS: USED 60/40 POZMIX 8% GEL BY HALLIBURTON. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID OBSERVE THIS PLUGGING.

SIGNED [Signature] (TECHNICIAN) FORM CP-2/3

[Handwritten mark]

11-4-98
60260