

4-17 15-055-00325-0006 353
API NUMBER 13- Drilled 6/2/50

To: 1 051429
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE NE NE SW, SEC. 22, T. 22 S, R. 34 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2540 feet from S section line
2740 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4058
Operator: American Warrior, Inc.
Name & Address: P.O. Box 399
Garden City, KS 67846

Lease Name Werner Well # 1
County Finney 87.88
Well Total Depth 2704 feet
Conductor Pipe: Size feet
Surface Casing: Size 7" feet ?

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Continental Energy License Number 5317

Address P.O. Box 918, Garden City, KS 67846

Company to plug at: Hour: 9 a.m. Day: 17 Month: 4 Year: 1991

Plugging proposal received from Kevin Wiles

(company name) Continental Energy (phone) 816-276-8710

were: 5 1/2" at 2699' w/? cement, PBTD 2583', Perfs at 2646-2516'
1st plug pump 1 sx hulls and 20 sx common cement to 2400',
2nd plug shoot casing at 1000', run tubing to 1000' and circulate cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:10 p.m. Day: 17 Month: 4 Year: 1991

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx common cement to 2400',

2nd plug shot 5 1/2" casing at 1000', could not pump cement. Ran tubing to 1000' and circulated cement with 110 sx.

Could not pump down 7" X 5 1/2" annulus.

Could not find 8 5/8" casing.

RECEIVED
STATE CORPORATION COMMISSION
4-2591 APR 25 1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

Signed Richard M. Lacey (TECHNICIAN)

INVOICED
DATE 5-7-91
INV. NO. 3176.1