

To: 1090475 9-19
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-055-21,332-0000

C SW, SEC. 3, 7 22 S, R 34 X/E
1320 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6234

Lease Name Strackeljohn Well # 3

Operator: Petroleum Production Management, Inc.

County Finney

Name & Address 209 E. William, Ste. 200

Well Total Depth 1997 64.90 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 354

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co., Inc. License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 5 p.m. Day: 19 Month: 9 Year: 1994

Plugging proposal received from Keith Van Pelt

(company name) Murfin Drilling Co., Inc. (phone) 316-267-3241

Work: to fill hole with heavy mud and spot cement through drill pipe

Drill pipe stuck in hole, shot off at 1435', laid down one joint

1st plug at 1400' with 40 sx cement, 2nd plug at 1100' with 80 sx cement,

3rd plug at 700' with 40 sx cement, 4th plug at 382' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:45 p.m. Day: 19 Month: 9 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 1400' with 40 sx cement,

2nd plug at 1100' with 80 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 382' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement. 562' drill pipe left in hole from 1435-1997'.

Remarks: Used 60/40 Pozmix 6% gel $\frac{1}{2}$ floseal by Allied.

INVOICED

(If additional description is necessary, use BACK of this form.)

I ~~check~~ / did not observe this plugging.

DATE 10-10-94

Signed [Signature]
(TECHNICIAN)

INV. NO. 41376

CARD MUST BE TYPED

State of Kansas

NO. 1

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL
HUGOTON INFILL

Starting Date: 8 month 9 day 1994 year

API Number 15-055-21332-0000
IS SECTION X REGULAR IRREGULAR?

OPERATOR: License # 6234
Name: Petroleum Production Management, Inc.
Address: 209 E. William, Suite 200
City/State/Zip: Wichita, KS 67202
Contact Person: Frank E. Novy, Sr., V.P.
Phone: (316) 265-4651

...C. SW. Sec. 3. Twp. 22. S. Rg. 34. W
1320 Ft. from South Line of Section
3960 Ft. from East Line of Section

NOTE: Attach acreage attribution plat locating both Chase (Hugoton) wells
Total number of acres attributed to unit .640
Nearest producing well from

CONTRACTOR: License # 30606
Name: Murfin Drilling Co., Inc.
City/State: Wichita, KS

same common source of supply 2640 feet
Nearest lease or unit boundary line 1320 feet
County: Finney

Well Drilled as: X New Recompletion OWWO
Projected Total Depth: 2800 feet
Formation: Chase

Lease Name: Strackeljohn Well # 3
Ground surface elevation: 2955 feet MSL
Depth to bottom of fresh water: 150'

If OWWO or Recompletion: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Depth to bottom of usable water: 1100'
Surface pipe by Alternate: 1-2 X
Surface pipe planned to be set: (350') 200'

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date: 7/20/94 Signature of Operator or Agent: Frank E. Novy, Sr. Title: Senior Vice President

For KCC Use:
Conductor Pipe Required: 0 feet; Minimum Surface Pipe Required: 200' feet per Alt. X
This Authorization Expires: 1-22-95 Approved By: CB 7-22-94

Pusher: Keith Ware Salt

SPUD DATE: 9-16-94 INIT. *rw*

LENGTH SURFACE PLANNED: 352

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt. sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 2 1/2 @ 354 CONDUCTOR
ANHYDRITE T- B- ELEVATION
TD 1997 FORMATION *Drill Pipe stuck in hole*
RAN PIF *5400' to 1435'*
RAT HC

WATER WELL SX (Irr. Well) Pond
TECHNICIAN *SM* DATE *9-18-94* Hauling
TYPE OF CEMENT *60/40 6 1/2 1 1/2 1/2 1/2*
STARTING TIME 5:00 (AM/PM) DATE 9-19-94
COMPLETION TIME 6:45 (AM/PM) DATE 9-19-94
CEMENT COMPANY *ALLI-D*

*362' Drill Pipe
Left in hole from 1435 to 1997' FS*

Put this on

AI	SX
HI	SX
AI	40 SX
I	80 SX
I	40 SX
B	50 SX
4	10 SX
RAT HC	1 SX