

TO: **1 090349** 11-1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-055-00317-0060
API NUMBER 15-Drill Completion 9/9/55
S/2 NW, SEC. 13, T 22 S, R 34 W/2
3340 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5293
Operator: Helmerich & Payne, Inc.
Name & Address: P.O. Box 558
Garden City, KS 67846

Lease Name Niquette Well # 1
County Finney
Well Total Depth 2611 84.85 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 284

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Helmerich & Payne, Inc. License Number 5293
Address P.O. Box 558, Garden City, KS 67846

Company to plug at: Hour: 10:30 a.m. Day: 1 Month: 11 Year: 19 93

Plugging proposal received from Mark
(company name) Helmerich & Payne, Inc. (phone) 316-276-3693

were: 7" at 2600' w/300 sx cement, Perfs at 2555-63, 2568-78, 2601-11'-Open hole
1st plug set CIBP at 2457' with 25 sx cement on top through bailer,
2nd plug perforate 7" casing at 1100' and pump in 281 sx cement,
3rd plug hook onto backside and pump in 144 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1:55 p.m. Day: 1 Month: 11 Year: 1993

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2457' and dumped 25 sx cement on top through bailer,
2nd plug perforated 7" casing at 1100' and pumped in 281 sx cement. Maximum pressure 580 psi and shut in 320 psi.
3rd plug hooked onto backside and pumped in 144 sx cement.
Maximum pressure 350 psi and shut in 80 psi.

RECEIVED STATE CORPORATION NOV 30 1993
NOV 03 1993

Remarks: Used 65/35 Pozmix 8% gel by Dowell Schlumberger. No casing recovery.
If additional description is necessary, use BACK of this form.

INVOICED
NOV 16 1993
DATE
INV. NO. 39194

Conservation Division
Wichita, Kansas
Signed _____ (TECHNICIAN)