

1 020391

8-8

512

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 13-055-21,018-0000

NE NE NE SEC. 16, T 22, S, R 34 W/E

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003

Lease Name Boyd "A" Well # 1-16

Operator: McCoy Petroleum Corporation

County Finney 162.50

Name & Address 110 S. Main, Suite 500

Well Total Depth 5000 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1986

Abandoned Oil Well Gas Well Input Well SWD Well D&A y

Other well as hereinafter indicated

Plugging Contractor BEREDCO License Number 5147

Address 401 E. Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 1:30 p.m. Day: 8 Month: 8 Year: 19 91

Plugging proposal received from Kenny

(company name) BEREDCO. (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2800' with 80 sx cement, 2nd plug at 2000' with 50 sx cement,

3rd plug at 1000' with 50 sx cement, 4th plug at 600' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:30 p.m. Day: 8 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2800' with 80 sx cement,

2nd plug at 2000' with 50 sx cement,

3rd plug at 1000' with 50 sx cement,

4th plug at 600' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Dowell.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 06 1991

INV. NO. 32973

RECEIVED

STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form.)

AUG 13 1991

CONSERVATION DIV. Wichita, Kansas

Signed Glenn R. Barlow (TECHNICIAN)

8-13-91