

1 100077

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 093-20,393-0000

NW SW NE, SEC. 4, T 22 S, R 35 (W) EX

3630 feet from N/S section line

2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5027

Lease Name Rooney "B" Well # 2

Operator: J. A. Allison

County Kearny 149.01

Name & Address 300 W. Douglas, Suite 305

Well Total Depth 4585 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 6:00 pm Day: 9 Month: October Year: 19 85

Plugging proposal received from Ronny Hoover

(company name) Kelso (phone) 316-938-2941

were: 5 1/2" at 4582' PBTD 4501', CIBP at 4512', Perfs at 4421-25'; 4449-51'; 4458-60';

4531-34'  
1st plug sand back to 4370' and dump 5 sx cement on top of sand through bailer

2nd plug if can't get pipe loose, pump 200 sx cement down 5 1/2" and 200 sx down 8 5/8"

Orders given by Richard W. Lacey

Plugging Proposal Received by *Blayne Wiley*  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:35 pm Day: 9 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4370' and dumped 5 sx cement on top of

sand through bailer, 2nd plug pumped 200 sx cement down 5 1/2" casing and pumped 200

sx cement down 8 5/8"

RECEIVED  
STATE CORPORATION COMMISSION

OCT 15 1985 10-15-85

Maximum pressure 500 psi and shut in 300 psi

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. No recovery.

(If additional description is necessary, use BACK of this form.)

(d) observe this plugging.

Signed *Blayne Wiley*  
(TECHNICIAN)

INVOICED

OCT 17 1985

DATE \_\_\_\_\_

INV. NO. 10635