

1-23

189
2-060238 R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

15-155-37452-0000
00-01

API NUMBER: 8/6/42 E-04,456

S&SE NW, SECTION 12 TOWNSHIP 23 RANGE 10W

OPERATOR LICENSE # 5447 2970 FEET FROM S SECTION LINE
3630 FEET FROM E SECTION LINE

OPERATOR Oxy USA Inc.
NAME & P. O. Box 26100
ADDRESS Oklahoma City, OK 73126-0100

LEASE NAME: Peace Creek Ut #2303W
COUNTY: Reno

WELL TOTAL DEPTH: 3763' 122.29
PIPE: 5-1/2" @ 3743'/75 sx
PIPE: 8-5/8" @ 261'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL X SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____
PLUGGING CONTRACTOR: Basye Well Servicing
ADDRESS: P. O. Box 149, Stafford, KS 67578 LICENSE: 5670

COMPANY TO PLUG AT: HOUR: _____ am DAY: 23 MONTH: 1 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Don Herman
COMPANY NAME: Oxy USA Inc. PHONE: 316-532-2002

WERE: Shoot off tub @ 3593' - leave packer & 93' tub in well
- dump bail 3 sx sd/5 sx cmt - perf @ 1410', 900' &
311' - run tub to 1410' & spot 30 sx cmt - pull tub to
900' & spot 30 sx - pull tub to 311' & circ 100 sx cmt
to surf - pump cmt between 5-1/2" & 8-5/8" to surf.

2-5-91

PLUGGING PROPOSAL RECEIVED BY: District #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART (_____) NONE (_____)

COMPLETED: HOUR: 4:45p DAY: 23 MONTH: 1 YEAR: 1991

FEB 5 1991
CONSERVATION DIVISION
Wichita, Kansas

ACTUAL PLUGGING REPORT:
Shot off tub @ 3593' - left pkr & 93' tub in well -
dump bailed 3 sx sd/5 sx cmt - perf @ 1410', 900' and
311' - ran tub to 1401' & spotted 30 sx cmt - pulled
tub to 914' & spotted 30 sx cmt - pulled tub to 325' &
pumped 115 sx cmt - not circ - ordered 65/35 poz 2%
gel, 3% cc - pulled out tub & filled 5-1/2" w/100 sx -
put 250# press on 5-1/2" - shut in @ 200# - no rec.

REMARKS: Howco #091997, 65/35 poz 6% gel, 3% cc

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE FEB 13 1991

Phil Worley
Phil Worley (AGENT)

INV. NO. 30715

FORM CP-2/3
REV. 3/90