

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009 21,357-0000

SE-SE-SW, Sec. 24, T 16 S, R 11 WE

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6293

Lease Name VANEK Well # 1

Operator: BROUGHER OIL INC.
Name & Address DRAWER 1264
GREAT BEND, MO.
67530

County BARTON

Well Total Depth 3373 feet \$109.62

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 273'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor MELSO CASING PULLING License Number 6050

Address BOX 176 CHASE, MAN'S. 67324

Company to plug at: Hour: 1:00 PM Day: 12th Month: OCT Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO MILLARD MELSO

(company name) MELSO CASING PULLING (phone) 216-938-2457

were: 8 5/8" - 273' SP. CUL. 1/200^{5/8} CNT., 4 1/2" OSG. SET @ 2364^{EL. 1/150} CNT.
PERFS. TOP 3060 EL, AT. BOTTOM PLUGGED 1/5^{5/8} CNT. SAND TO
3000^{EL} AND 1/5^{5/8} CNT., SHOT PIPE 3 TIMES RECOVERED 2121 EL
ORDERED 165^{5/8} 50/50 FORMIX 4% GEL - 3% CA-CL., 15^{5/8} GEL, 5^{5/8} HULLS.
AND 8 5/8" PLUG, PUMP IN 8 5/8" S.P.

Signed Millard Melso
(TECHNICIAN) DDK

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 PM Day: 13th Month: OCT. Year: 1983

ACTUAL PLUGGING REPORT

ORDERED 165^{5/8} 50/50 FORMIX 4% GEL - 3% CA-CL., 15^{5/8} GEL,
5^{5/8} HULLS. AND 8 5/8" PLUG. PUMPED IN WITH PUMP TRUCK.
PUMPED IN 8 5/8" 4^{5/8} HULLS - 25^{5/8} CNT. - 12^{5/8} GEL - 1/2^{5/8} HULLS,
40^{5/8} CNT., 3^{5/8} GEL, 1/2^{5/8} HULLS, AND RELEASED PLUG.
AND 100^{5/8} CNT. MAX. PRESSURE 150 PSI (REM. BY HALLIBURTON)

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED
DATE 10-26-83
INV. NO. 5888-W

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1983
CONSERVATION DIVISION
Wichita, Kansas

Signed Millard Melso
(TECHNICIAN) DDK