

6-050123

9-14

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-03043-0000

*AMB
NE
ECC*

NW SE NW /4 SEC. 18, 16 S, 11 W
3630 feet from S section line
2970 feet from E section line

Operator license# 4656 Lease Krier well # 7

Operator: Davis Petroleum County Barton

Address: R. R. 1, Box 183 B Well total depth 3285 feet
Great Bend, Kansas 67530 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 240 feet

106.76

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Davis Petroleum License#

Address: As above

Company to plug at: Hour: PM Day: 14 Month: September Year: 1993

Plugging proposal received from: L. D. Davis

Company: Davis Petroleum phone: 316-793-3051

Were: 8 5/8" set at 240' w 100 sx. 5 1/2" set at 3261' w 100 sx.
4 1/2" liner set at 2764 w 100 sx. Base salt section at 1450', Anhydrite
at 710', Dakota at 467'. Emergency plug. Permanent plug set at 2700'.
Run tubing to 2700', cement with 75 sx 50/50 poz mix, 3% cc. Pull to 1700',
cement with 75 sx 50/50 poz mix, pull to 700', cement till circulate,
pull tubing and squeeze down 4 1/2" casing. Squeeze annular spaces.
300 sx 50/50 poz 3%cc on location.

Plugging Proposal Received by: Marion Schmidt
Plugging operations attended by agent? All[XXX], Part[], None[]

Completed: Hour: 3:50 PM, Day: 14, Month: September, Year: 1993

Actual plugging report: Set permanent cast iron plug at 2700'. Ran tubing
to 2650'. Pumped 75 sx 50/50 poz, 3% cc. Pull tubing to 1650'. Pumped 75
sx 50/50 poz, 3%cc. Pull tubing to 650'. Pumped 150 sx 50/50 poz 3% cc,
cement did not circulate. Ran wireline to 1263'. Pulled tubing. Pumped
20 sx gel, 50 sx 60/40 8% gel down 4 1/2" liner. Vacuum on well head.
Set permanent plug at 750'. Pump 50 sx 60/40 poz 8% gel, 950# max, 300#
shut in. 4 1/2"-5 1/2" annular space 6 sx 60/40 poz 8% gel, 300# shut in.
8 5/8"-5 1/2" annular space, no cement, pressure to 50#

Remarks: Halliburton on location
Condition of casing(in hole):GOOD BAD XX Anhy. plug: YES X NO RECEIVED
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X NO CORPORATION COMMISSIO
Plugged through TUBING XXX, CASING XXX Elevation: 1867 GL

9-28-93

I did INVOICED not observe the plugging.

Bruce D. Basy
Bruce D. Basy
(agent) CONSERVATION DIVISION
Wichita, Kansas

DATE 9-28-93

INV. NO. 38790

9-14 NOV 15 1993