

062301

12-27

API NUMBER 15-

009-23,781

259
6000
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW, SEC. 18, T 16 S, R 11 WAB
3960 feet from S section line
3510 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Krier A Well # 2

Operator: L. D. Drilling Inc.
Name & Address: R.R. #1 Box 183 B
Great Bend, Ks. 67530

County Barton 106.76
Well Total Depth 3285 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____

Address Great Bend, Ks. 67530

Company to plug at: Hour: 2:00 PM Day: 27 Month: Dec. Year: 19 90

Plugging proposal received from L. D. Davis

(company name) L. D. Drilling Inc. (phone) 316-793-301

were: Order 200 sks of 60/40 poz 8% gel 5 sks hulls.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: Part _____ None _____

Operations Completed: Hour: 3:00 PM Day: 27 Month: Dec. Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8 set at 343 w/200 sks. 5 1/2 set at 3283 w/150 sks.

Plugged bottom w/sand and 5 sks cement to 3225. Shot pipe one time and
recovered 2400. Pumped in 8 5/8 25 sks cement followed w/5 sks hulls in 175 sks
cement w/1000 psi.

RECEIVED
STATE CORPORATION COMMISSION
01-07-91
JAN 7 1991

Remarks: by Halliburton Ran line to 1500.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

Signed *Gilbert G. Scheck*
(TECHNICIAN) e.a.f.
Gilbert G. Scheck

INVOICED

JAN 18 1991

DATE

INV. NO.

30530