

4 060211

7-2

77

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
270 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 009-23,793 D-23,790

SE NE SW, SEC. 18, T 16 S, R 11 W/E  
1650 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9354

Lease Name Hoffman Well # 2

Operator: Central Energy Corporation

County Barton 119.95

Name & Address P.O. Box 47590

Well Total Depth 3691 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 405

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well XXXXX D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Great Bend, KS

Company to plug at: Hour: 9:30AM Day: 2 Month: July Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) \_\_\_\_\_

Order 250 sxs. 60/40 Pos 8%gel

Sand back to 50' above perforations and spot 7 sxs. cement.

Tubing in hole had been pulled prior to plugging off bottom.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 11 1991  
CONSERVATION DIVISION  
Wichita, Kansas

07-11-91

Plugging Proposal Received by Herb Deines  
(TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXXXX Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30AM Day: 2 Month: July Year: 19 91

ACTUAL PLUGGING REPORT 10 3/4" to 405', 7" to 3682. Sand back to 3350' and spot 7 sxs. cement.  
Shot casing at 744' but wouldn't pull free. Spotted 50 sxs. cement. Shot casing at 400'  
and circulated cement to surface with 135 sxs. cement. Pulled casing and topped off with  
with cement. Recovered 400' of 7".

Remarks: Allied Cementing  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(If ~~XXXXXX~~ observe this plugging.

DATE 7-22-91

Signed Herb Deines  
(TECHNICIAN)

INV. NO. 32353

Herb Deines

Herb Deines