

4-062684

9-24

105
D

15-009-15185-0091

D-04,453

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1955

SE SE NE /4 SEC. 18, 16 S, 11 W
2970 feet from S section line
330 feet from E section line

Operator license# 4252 Lease Schartz well # 1

Operator: Kahan & Associates, Inc. County Barton

Address: P.O. Box 559 Well total depth 3474 feet
Tulsa, Oklahoma 74101 Conductor Pipe: 12 inch @ 196 feet
918-587-4159 Surface pipe 8 5/8 Inch @ 2820 feet

112.90

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: Box 347, Chase, Kansas 67524

Company to plug at: Hour: 9:30A.M. Day: 24 Month: September Year: 92

Plugging proposal received from: David M. Wilson

Company: Kelso Casing Pulling, Inc. Phone: 316-938-2943

Were: Order 500 sks. of 60/40 posmix - 8% gel. - 5 sks. hulls.

Plugging Proposal Received by: Gilbert G. Scheck

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 4:00P.M., Day: 24, Month: September, Year: 92

Actual plugging report: 12" @ 196' w/75 sks. 8 5/8" @ 2820' w/250 sks.

Pump in 12" surface w/50 sks. cement. Max. pressure 300#. Shut in

300#. Mixed approximately 40 sks. 60/40 pozmix - 8% gel. with 100#

hulls down 8 5/8" casing. Max. pressure with 700#. Shut in with 500#.

Mixed approximately 230 sks. 60/40 pozmix - 8% gel. with 250 # hulls

down 5" casing. Max. pressure with 1700#. Shut in with 700#.

7" @ 3293' w/75 sks. Cement lined tubing 5" and 3326'.

Max. pressure on 8 5/8" - 700 P.S.I. Shut in @ 500 P.S.I.

Max. pressure on backside - 1700 P.S.I. Shut in @ 700 P.S.I.

Remarks: Total sacks 320 cement.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES 710 NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 1835 GL

9-30-92

RECEIVED
STATE CORPORATION COMMISS

SEP 30 1992

CONSERVATION DIVISION
Wichita, Kansas

I did[X] / did not[] observe the plugging.

Gilbert G. Scheck

(agent)

Form CP-2/3

INVOICED

DATE 10-6-92

INV. NO. 36324