

2040111

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-095-21484-0680

TECHNICIAN'S PLUGGING REPORT

Operator License # 5/23

Lease Name Deperkushwell # A 3

Operator Name: Pickrell Drls.

County Kingman

Address 110 Litwin Bldg.

Well Total Depth 4360 141.70 feet

Wichita Ks.

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 221

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drls. License Number _____

Address 110 Litwin Bldg Wichita Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Gary Christopher

(company name) Pickrell Drls. (phone) _____

were: 35 sx 1100

35 sx 250

20 sx 40

20 sx RH

8 sx WW

RECEIVED
STATE CORPORATION COMMISSION
SEP 05 10 09 AM '84
9-5-84
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Glen Word
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1710 Day: 23 Month: 8 Year: 19 84

ACTUAL PLUGGING REPORT Fill hole with heavy mud, Run drill pipe to 1100 feet and spot 35 sacks of cement, pull pipe to 250' and spot 35 sacks of cement. Pull pipe from hole, dump 1/2 sack of hulls and push Rubber plug to 40' and circulate hole full. Put drill pipe in Rat hole and circulate with 20 sacks of cement. Fill Water well with cement. (F.L. 30')

Remarks: Allied Cementing (GB) # 38282
(If additional description is necessary, use BACK of this form.)

IN V(initials) C(initials) E(initials) D(initials) observe this plugging.

DATE 9-12-84

WK

Signed Stu W. Bean
(TECHNICIAN)

INV. NO. 3637

RO

8-23